6 BIODIVERSITY

6.1 Introduction

This Biodiversity Chapter assesses the potential effects of the Proposed Development on habitats and species; particularly those protected by national and international legislation or considered to be of particular nature conservation importance on or adjacent to the Site. This report will describe the ecology of the Site, with emphasis on habitats, flora and fauna, and will assesses the potential effects of the Construction and Operational Phases of the Proposed Development on these ecological receptors. The report follows Guidelines for Ecological Impact Assessment in the UK and Ireland, by the Chartered Institute of Ecology and Environmental Management (CIEEM, 2024) and supplemented by the National Roads Authority (2009) guidelines for Assessment of Ecological Impacts of National Road Schemes. The purpose of this Chapter is to:

- Set out the methodologies used to inform the assessment.
- Identify Key Ecological Receptors (KERs) within the Zone of Influence (ZOI).
- Assess the impacts from the Proposed Development on the KERs and the resulting significant effects.
- Set out measures to avoid or mitigate negative impacts.
- Assess the residual effects after the incorporation of agreed avoidance or mitigation measures to ensure legal compliance.
- Set out agreed measures to offset significant residual effects.
- Set out opportunities for ecological enhancement.

6.1.1 Quality Assurance and Competency of Experts

All surveying and reporting have been carried out by qualified and experienced ecologists and environmental consultants. Charith Rakesh Kumar (CRK), Ecologist with Enviroguide authored and undertook the field surveys for this report.

CRK is an Ecologist with a M.Sc. in Biodiversity and Conservation from Trinity College Dublin. CRK's experience as an ecologist is broad both variety of ecological reports and literature, and field surveys conducted. CRK has experience in surveying habitats, birds, plants, bats, mammals and invasive species, with some experience in assessing welfare conditions of animals using behavioural repertoires as indicators. CRK's experience in ecological report writing extends from Research associated reporting to Appropriate Assessment (AA) Screening reports, Natura 200 Impact (NIS) reports, Preliminary Environmental Assessment (PEA) reports, and Ecological Impact Assessment (EcIA) reports.

6.1.2 Relevant Legislation and Policy Context

There is a number of pieces of legislation, regulations and policies specific to ecology which underpin this assessment. These may be applicable at a European, National or Local level. Legislation at the International level relevant to the Proposed Development are listed below:

- Council Directive 92/43/EEC on the Conservation of Natural Habitats and of Wild Fauna and Flora; hereafter the 'Habitats Directive'.
- Directive 2009/147/EEC, hereafter the 'Birds Directive'.
- Directive 2011/92/EU, hereafter the 'EIA Directive'.
- EU Regulation 1143/2014, on Invasive Alien Species.
- Convention on the Conservation of European Wildlife and Natural Habitats 1982, hereafter the 'Bern Convention'
- The Convention on the Conservation of Migratory Species of Wild Animals 1983, hereafter the 'Bonn Convention'.
- Ramsar Convention on Wetlands 1971, hereafter referred to as 'Ramsar'.
- Water Framework Directive 2000/60/EC, hereafter the 'WFD'.

National legislation and policy relevant to the Proposed Development are listed below:

- Wildlife Act 1976, as amended in 2000.
- Flora (Protection) Order 2022.
- The Planning and Development Act 2024 as amended.
- National Biodiversity Plan 2023 2030.

Additionally, Natural Heritage Areas (NHAs) are designations under the Wildlife Acts to protect habitats, species, or geology of national importance. The boundaries of many of the NHAs in Ireland overlap with Special Areas of Conservation (SAC) and/or Special Protection Area (SPA) sites. Although many NHA designations are not yet fully in force under this legislation (referred to as 'proposed NHAs' or pNHAs), they are offered protection in the meantime under planning policy which normally requires that planning authorities give recognition to their ecological value.

Local plans and policies relevant to the Proposed Development are listed below:

- Fingal Development Plan 2022-2028
- Fingal Biodiversity Action Plan 2023-2030

6.1.3 Assessment Methodology

This Biodiversity Chapter has been undertaken to support and assess the Proposed Development planning application and assesses the potential impacts that the Proposed Development may have on the ecology of the Site and its environs. Where potential for a risk to the environment is identified, mitigation measures are proposed on the basis that by deploying these mitigation measures the risk is eliminated or reduced to an insignificant level.

This section details the steps and methodology employed to undertake an ecological impact assessment of the Proposed Development.

6.1.4 Nature Conservation Importance

Determining 'importance' of ecological features relies on professional judgement and includes consideration of factors such as size, conservation status and quality, as well as the policy and legal significance. 'Importance' is measured against published selection criteria where available and with reference to published lists (e.g. CIEEM Guidelines for Ecological Impact Assessment). 'Importance' should take into account potential for future restoration of habitats, species populations or ecosystems, which are currently in unfavourable or sub-optimal condition. It should also take into account the importance of the feature to other important features (e.g. a low quality habitat that will allow migration of an adjacent high quality habitat as a consequence of climate change, stepping stone habitats for migratory species or species dispersal).

It should be noted that some species are subject to legal protection that varies through the year (e.g. birds have special protection during the breeding season), or that does not relate to conservation status (e.g. badgers which are subject to protection primarily on animal welfare grounds). Where protected species are present and there is potential for a breach of the legislation, those features are considered as 'important' features. Legally controlled species, e.g. species listed on Schedule 9 of the Wildlife and Countryside Act 1981 (as amended), are also considered to ensure that land-use changes do not result in contravention of legislation.

The CIEEM Guidelines for Ecological Impact Assessment recommend that the importance of each ecological feature is described in terms of its geographic frame of reference. To achieve no net loss of biodiversity and maintenance of healthy ecosystems this impact assessment will consider impacts at all scales.

Table 6.1 below provides the definitions used for various Ecological Receptors as per their associated value or importance across different levels.

Table 6.1: Evaluation of Ecological Receptor

Value/	
Importance	Criteria
International (European)	 'European Site' including Special Area of Conservation (SAC), Site of Community Importance (SCI), Special Protection Area (SPA) or proposed Special Area of Conservation. Proposed Special Protection Area (pSPA) Site that fulfils the criteria for designation as a 'European Site' (see Annex III of the Habitats Directive, as amended). Features essential to maintaining the coherence of the Natura 2000 Network Site containing 'best examples' of the habitat types listed in Annex I of the Habitats Directive. Resident or regularly occurring populations (assessed to be important at the national level) of the following: Species of bird, listed in Annex I and/or referred to in Article 4(2) of the Birds Directive; and/or Species of animal and plants listed in Annex II and/or IV of the Habitats Directive Ramsar Site (Convention on Wetlands of International Importance Especially Waterfowl Habitat 1971). World Heritage Site (Convention for the Protection of World Cultural & Natural Heritage, 1972). Biosphere Reserve (UNESCO Man & The Biosphere Programme) Site hosting significant species populations under the Bonn Convention (Convention on the Conservation of Migratory Species of Wild Animals, 1979). Site hosting significant populations under the Berne Convention (Convention on the Conservation of European Wildlife and Natural Habitats, 1979). Biogenetic Reserve under the Council of Europe. European Diploma Site under the Council of Europe. Salmonid water designated pursuant to the European Communities (Quality of
National (Ireland)	 Salmonid Waters) Regulations, 1988, (S.I. No. 293 of 1988). Site designated or proposed as a Natural Heritage Area (NHA). Statutory Nature Reserve. Refuge for Fauna and Flora protected under the Wildlife Acts. National Park. Undesignated site fulfilling the criteria for designation as a Natural Heritage Area (NHA); Statutory Nature Reserve; Refuge for Fauna and Flora protected under the Wildlife Act; and/or a National Park. Resident or regularly occurring populations (assessed to be important at the national level) of the following: Species protected under the Wildlife Acts; and/or Species listed on the relevant Red Data list. Site containing 'viable areas' of the habitat types listed in Annex I of the Habitats Directive
Regional (County Dublin)	 Area of Special Amenity. Area subject to a Tree Preservation Order. Area of High Amenity, or equivalent, designated under the County Development Plan. Resident or regularly occurring populations (assessed to be important at the County level) of the following: Species of bird, listed in Annex I and/or referred to in Article 4(2) of the Birds Directive; Species of animal and plants listed in Annex II and/or IV of the Habitats Directive; Species protected under the Wildlife Acts; and/or Species listed on the relevant Red Data list.

- Site containing area or areas of the habitat types listed in Annex I of the Habitats Directive that do not fulfil the criteria for valuation as of International or National importance.
- County important populations of species; or viable areas of semi-natural habitats; or natural heritage features identified in the National or Local BAP; if this has been prepared.
- Sites containing semi-natural habitat types with high biodiversity in a county context and a high degree of naturalness, or populations of species that are uncommon within the county.
- Sites containing habitats and species that are rare or are undergoing a decline in quality or extent at a national level.
- Area of Special Amenity.
- Area subject to a Tree Preservation Order.
- Area of High Amenity, or equivalent, designated under the County Development Plan.
- Resident or regularly occurring populations (assessed to be important at the County level) of the following:
 - Species of bird, listed in Annex I and/or referred to in Article 4(2) of the Birds Directive;
 - Species of animal and plants listed in Annex II and/or IV of the Habitats Directive;
 - Species protected under the Wildlife Acts; and/or
 - Species listed on the relevant Red Data list.
 - Site containing area or areas of the habitat types listed in Annex I of the Habitats Directive that do not fulfil the criteria for valuation as of International or National importance.
- County important populations of species; or viable areas of semi-natural habitats; or natural heritage features identified in the National or Local BAP; if this has been prepared.
- Sites containing semi-natural habitat types with high biodiversity in a county context and a high degree of naturalness, or populations of species that are uncommon within the county.
- Sites containing habitats and species that are rare or are undergoing a decline in quality or extent at a national level.
- Locally important populations of priority species or habitats or natural heritage features identified in the Local BAP, if this has been prepared;
- Sites or features containing common or lower value habitats, including naturalised species that are nevertheless essential in maintaining links and ecological corridors between features of higher ecological value.
- Resident or regularly occurring populations (assessed to be important at the Local level) of the following:
 - Species of bird, listed in Annex I and/or referred to in Article 4(2) of the Birds Directive;
 - Species of animal and plants listed in Annex II and/or IV of the Habitats Directive;
 - o Species protected under the Wildlife Acts; and/or o
 - o Species listed on the relevant Red Data list.
 - Sites containing semi-natural habitat types with high biodiversity in a local context and a high degree of naturalness, or populations of species that are uncommon in the locality;

Sites or features containing common or lower value habitats, including naturalised species that are nevertheless essential in maintaining links and ecological corridors between features of higher ecological value.

 Sites or features containing common or lower value habitats, including naturalised species that are nevertheless essential in maintaining links and ecological corridors between features of higher ecological value.

Authority Area (Fingal County Council)

Local (immediate Area) Full justification is provided in the assessment for those ecological features that have been recorded in the study area but have been identified as being not 'important'. Those features are scoped out and not assessed further in the EcIA.

6.1.5 Assessment of Effects

The assessment of the potential effects of the proposed scheme considers both on-site effects and those that may occur to adjacent and more distant nature conservation receptors. Impacts on nature conservation receptors have been characterised, including consideration of:

- Positive or negative (e.g. adverse/beneficial);
- Duration (e.g. permanent/temporary);
- Reversibility (e.g. irreversible/reversible)
- Extent/magnitude;
- Frequency and timing.

Impacts can occur during construction and/or operation, can be permanent or temporary and can include:

- Direct loss of habitats (including temporary loss);
- Fragmentation and isolation of habitats;
- Disturbance to species from noise, light or other visual stimuli;
- Changes to key habitat features;
- Changes to the local hydrology, water quality and/or air quality; and
- Direct mortality or injury to wildlife through construction activities and/or operation.

The significance of effect on an ecological receptor is assessed by considering the environmental sensitivity or value of the receptor and the magnitude of impact. However, effects on conservation status have only been assessed in detail for ecological receptors of local value for biodiversity or greater, and which could be affected by the proposed scheme. Effects on receptors of Less than Local value for biodiversity have been scoped out of further assessment.

The level of impact on biodiversity resources has been assigned as outlined within Table 6.. Where more than one significance outcome is possible, professional judgement has been used to determine which is most appropriate, on a case by case basis, and ensuring regard to the precautionary principle.

Table 6.2: Impact Magnitude and Character for Ecological Features

Level of Impact (Change)	Impact Cha	Impact Characteristics			
		Permanent/ irreversible damage to a biodiversity resource; and			
Major	Adverse	2) The extent, magnitude, frequency, and/or timing of an impact negatively affects the integrity or key characteristics of the resource.			
	Beneficial	Permanent addition of, improvement to, or restoration of a biodiversity resource; and			
		The extent, magnitude, frequency, and/or timing of an impact			

		positively affects the integrity or key characteristics of the resource
		Temporary/reversible damage to a biodiversity resource; and
	Adverse	2) The extent, magnitude, frequency, and/or timing of an impact negatively affects the integrity or key characteristics of the resource.
Moderate		Temporary addition of, improvement to, or restoration of a biodiversity resource; and
	Beneficial	2) The extent, magnitude, frequency, and/or timing of an impact positively affects the integrity or key characteristics of the resource.
		Permanent and irreversible damage to a biodiversity resource; and
	Adverse	2) The extent, magnitude, frequency, and/or timing of an impact does not affect the integrity or key characteristics of the resource.
Minor		Permanent addition of, improvement to, or restoration of a biodiversity resource; and
	Beneficial	2) The extent, magnitude, frequency, and/or timing of an impact does not affect the integrity or key characteristics of the resource.
		Temporary and reversible damage to a biodiversity resource; and
	Adverse	2) The extent, magnitude, frequency, and/or timing of an impact does not affect the integrity or key characteristics of the resource.
Negligible		Temporary addition of, improvement to, or restoration of a biodiversity resource; and
	Beneficial	2) The extent, magnitude, frequency, and/or timing of an impact does not affect the integrity or key characteristics of the resource.
No Change	No observable impact,	either positive or negative

6.1.6 Significance of Effects

When determining the significance of an effect, consideration is given to whether:

- any processes or key characteristics will be removed or changed;
- there will be an effect on the nature, extent, structure and function of component habitats; and
- there is an effect on the average population size and viability of component species.

Functions and processes acting outside the formal boundary of a designated site have also been considered, particularly where a site falls within a wider ecosystem, or where areas of land are functionally linked to the designated sites (for example, habitats used occasionally for grazing by notable bird species but aren't included within the designated site boundary).

Some habitats and ecosystems can tolerate a degree of minor change, such as localised or temporary disturbance or changes in physical conditions, without such changes harming their function or value. Ecological effects have considered information available about the capacity of ecosystems to accommodate change.

The conservation status of undesignated habitats and species within a defined geographical area has been used to determine whether the effects of the proposals are likely to be significant:

- For habitats, conservation status is determined by the sum of the influences acting on the habitat that may affect its extent, structure and functions as well as its distribution and its typical species within a given geographical area; and
- For species, conservation status is determined by the sum of influences acting on the species concerned that may affect its abundance and distribution within a given geographical area.

The principles of the mitigation hierarchy have been applied when considering impacts and subsequent effects on nature conservation receptors within the ZoI. The principles state that in order of preference, impacts on biodiversity should be avoided, reduced, then remediated. If there are significant residual adverse effects that cannot be mitigated, then compensation will be required. Enhancement measures are also identified to provide benefits for biodiversity above the requirements for avoidance, mitigation or compensation.

Taking mitigation into account, the significance of residual effects on nature conservation receptors has been identified using professional judgement. The significance of residual effects is defined in Table 6.2.

Table 6.2: Significance of residual effects

		Level of Impact					
		No Change	Negligible	Minor	Moderate	Major	
	International or European importance	Neutral	Slight	Moderate or large	Large or very large	Very large	
Resource	UK or national importance	Neutral	Slight	Slight or moderate	Moderate or large	Large of very large	
Importance	Regional importance	Neutral	Neutral or slight	Slight	Moderate	Moderate or large	
	County or equivalent authority importance	Neutral	Neutral or slight	Neutral or slight	Slight	Slight or moderate	
	Local importance	Neutral	Neutral or slight	Neutral or slight	Neutral or slight	Slight	

6.1.7 Mitigation Hierarchy and Delivery

The approach to mitigation for impacts on natural conservation resources is to adhere to the mitigation hierarchy, as follows:

- Avoid impacts are avoided through measures incorporated into the design and good working practices;
- Mitigate impacts are reduced where possible to a level that the effect on the nature conservation resource is not significant through measures implemented through the design, construction and operation phases;
- Compensate impacts that are unavoidable and where mitigation does not reduce the effect to a level that is not significant are compensated for through creation or provision of new resources, such as habitat or places of shelter for animals.

6.1.8 Baseline Conditions and Importance

The following sections describe those features of ecological value relevant to the study area that have been identified through the data collection processes.

For each feature of interest, the following factors have been considered:

- Current condition / status of the habitat or species within the study area;
- Factors upon which the conservation status or integrity of the feature depends; and,
- Value of the feature, including the consideration of its significance on different geographical scales.

6.1.9 Scope of Assessment

The specific objectives of the study were to:

- Undertake baseline ecological surveys and evaluate the nature conservation importance of the Site:
- Identify and assess the direct, indirect and cumulative ecological implications or impacts of the Proposed Development during its lifetime; and
- Where possible, propose mitigation measures to remove or reduce those impacts at the appropriate stage of the Proposed Development.

6.1.10 Desk Study

A desktop study was carried out to collate and review available information, datasets and documentation sources pertaining to the Site's natural environment. The desk study, completed in April 2025, relied on the following sources:

- Information on species records and distributions, obtained from the National Biodiversity Data Centre (NBDC) at maps.biodiversityireland.ie;
- Information on Floral Protection Order (FPO) Bryophytes database at dahg.maps.arcgis.com;
- Information on waterbodies, catchment areas and hydrological connections obtained from the Environmental Protection Agency (EPA) at gis.epa.ie;
- Information on bedrock, groundwater, aquifers and their statuses, obtained from Geological Survey Ireland (GSI) at www.gsi.ie;

- Information on the network designated conservation sites, site boundaries, qualifying interests and conservation objectives, obtained from the National Parks and Wildlife Service (NPWS) at www.npws.ie;
- Satellite imagery and mapping obtained from various sources and dates including Google, Digital Globe, Bing and Ordnance Survey Ireland;
- Information on the existence of permitted development, or developments awaiting decision, in
 the vicinity of the Proposed Development from the National Planning Application Database
 available
 at:
 https://housinggovie.maps.arcgis.com/apps/webappviewer/index.html?id=9cf2a09799d74d8e
 9316a3d3a4d3a8de; and
- Information on the extent, nature and location of the Proposed Development, provided by the applicant and/or their design team.

A comprehensive list of all the specific documents and information sources consulted in the completion of this report is provided in the References section.

6.1.10.1 Bats

The Bat Conservation Ireland Landscape Suitability Model (Lundy *et al.*, 2011) provides a habitat suitability index for bat species across Ireland. The model divides the country into grid squares and ranks the habitat within the squares according to its suitability for various bat species. The scores are divided into five qualitative categories of suitability, namely:

- 0.0000000 13.000000: Low.
- 13.000001 21.333300: Low Medium
- 21.333301 28.111099: Medium
- 28.111100 36.444401: Medium High
- 36.444402 58.555599: High

Additionally, the NBDC website (<u>www.nbdc.ie</u>) was also interrogated for historical records of bats within the O03 10km grid square encompassing the Site of the Proposed Development. According to Collins (2023), Irish bats typically have a Core Sustenance Zone (CSZ) of under 5km. A CSZ is defined as "the area surrounding a communal bat roost within which habitat availability and quality will have a significant influence on the resilience and conservation status of the colony using the roost". A study by Sheil et al., (1999) found Leisler's bats (*Nyctalus leisleri*) had a maximum foraging range of 13.4km. A similar study by Waters et al., (1999) found Leisler's bats flew a mean maximum distance of 4.2km from the roost. The NBDC database offers a maximum search range of 10km. Therefore, this distance was chosen as the most suitable range to assess the likely impacts on bat foraging and commuting.

6.1.10.2 Zone of Influence

The ZOI for a project is the area over which ecological features may be affected by changes as a result of the Proposed Development and associated activities. This is likely to extend beyond the development site, for example where there are ecological or hydrological links beyond the site boundaries (CIEEM, 2018). The ZOI will vary with different ecological features, depending on their sensitivities to an environmental change.

Furthermore, ZOI in relation to European sites is described as follows in the 'OPR Practice Note PN01 - Appropriate Assessment Screening for Development Management' (OPR, 2021):

"The zone of influence of a proposed development is the geographical area over which it could affect the receiving environment in a way that could have significant effects on the Qualifying Interests of a European site. This should be established on a case-by-case basis using the Source-Pathway-Receptor framework and not by arbitrary distances (such as 15 km)."

6.1.10.3 Identification of Relevant Designated Sites

To determine the ZOI of the Proposed Development for designated sites, reference was made to the OPR Practice Note PN01 - Appropriate Assessment Screening for Development Management' (OPR, 2021), a practice note produced by the Office of the Planning Regulator, Dublin. This note was published to provide guidance on screening for AA during the planning process, and although it focuses on the approach a planning authority should take in screening for AA, the methodology is also readily applied in the preparation of EcIA reports such as this to identify all relevant designated sites potentially linked to the Proposed Development.

As noted above, the most recent guidance advises against the use of arbitrary distances that serve as precautionary ZOI (e.g., 15km), and instead recommends the application of the Source-Pathway-Receptor (S-P-R) model in the identification of designated sites, stating that "This should avoid lengthy descriptions of European sites, regardless of whether they are relevant to the proposed development, and a lack of focus on the relevant European sites and issues of importance". Although this statement refers to European sites, it is also applicable to other designated sites.

Thus, the methodology used to identify relevant designated sites comprised the following:

- Identification of potential sources of effects based on the Proposed Development description and details:
- Identification of potential pathways between the Site of the Proposed Development and any designated sites within the ZOI of any of the identified sources of effects.
- Water catchment data from the EPA (<u>www.epa.ie</u>) were used to establish or discount potential hydrological connectivity between the Proposed Development and any designated sites.
- Groundwater and bedrock information used to establish or discount potential hydrogeological connectivity between the Proposed Development and any designated sites.
- Air and land connectivity assessed based on Proposed Development details and proximity to designated sites.
- o Consideration of potential indirect pathways, e.g., impacts to flight paths, ex-situ habitats, etc.
- Review of Ireland's designated sites to identify those sites which could potentially be affected by the Proposed Development in view of the identified pathways, using the following sources;
- European sites and nationally designated sites (e.g., NHAs and pNHAs) from the NPWS (<u>www.npws.ie</u>);
- Ramsar sites from the Irish Ramsar Wetland Committee (https://irishwetlands.ie/irish-sites/);
- Other internationally designated sites e.g., United Nations Educational, Scientific and Cultural Organization (UNESCO) Biospheres; and
- Regional development plans to identify any remaining sites or areas designated for nature conservation at a local level.

6.2 Receiving Environment

This section sets out the baseline conditions for the ecological features within the respective plots of the Site using the findings of the desk study and field surveys.

6.2.1 Proposed Development – Plot 1 (Luttrellstown Gate Phase 2)

6.2.1.1 Geology, Hydrogeology, and Geology

The Proposed Development – Plot 1 (Luttrellstown Gate Phase 2) is located within the Liffey_SC_100 sub catchment within the Liffey and Dublin Bay catchment. The nearest mapped watercourse to Plot 1, namely Royal Canal Main Line (Liffey and Dublin Bay) (IE_09_AWB_RCMLE) stream is located approximately 45m to the north (EPA, 2025). This watercourse is classified as being of 'Good' qualify for the survey period 2016 – 2021. There are no Q-values available for along the length of this stream. The Royal Canal Main Line (Liffey and Dublin Bay) flows east then southeast for approximately 12.5km from the Proposed Development, before discharging into the Liffey Estuary Lower (IE_EA_090_0300) transitional waterbody. This then ultimately flows into the Dublin Bay (IE_EA_090_0000) coastal waterbody, which is located 17km downstream of the Proposed Project.

The groundwater body underlying the Site is the Dublin (IE_EA_G_008), which is classed as being of 'Good' water quality for the 2016 – 2021 survey period. The bedrock aquifer identified beneath the Site is mapped as "Poor Aquifer - Bedrock which is Generally Unproductive except for Local Zones" (PI), with a small section along the northern boundary classed as "Locally Important Aquifer - Bedrock which is Moderately Productive only in Local Zones" (LI). The Groundwater Vulnerability Rating assigned to groundwater beneath this plot of the Site is mapped as "Extreme" (E) for the predominant area, and "High" (H) for the southwest section of the Site (GSI, 2025).

The soil beneath the Site comprises "Fine loamy drift with limestones". The quaternary sediments beneath the Site are mapped as "Till derived from limestones" (TLs) while the subsoils beneath the Site are mapped as "Limestone till (Carboniferous)" (TLs) (GSI, 2025)

The Waterbody Status for river, groundwater, transitional and coastal water bodies relevant to the Site as recorded by the EPA (2025) in accordance with European Communities (Water Policy) Regulations 2003 (SI no. 722/2003) are provided in Table 6.3.

Table 6.3: WFD Risk and Waterbody Status

Waterbody Name	Water body; EU code	Distance from Site (km)	WFD water body status (2016-2021)	WFD 3 rd cycle Risk Status	Hydraulic Connection to the Site
		Surface Water B	Bodies		
Royal Canal Main Line (Liffey and Dublin Bay)	IE_09_AWB_RCMLE	45m N	Good	Review	None
	Т	ransitional Wate	r Bodies		
Liffey Estuary Lower	IE_EA_090_0300	12.5km SE	Moderate	At Risk	Downstream
		Coastal Water B	Bodies		
Dublin Bay	IE_EA_090_0000	17km E	Good	Not at Risk	Downstream
	Groundwater Bodies				
Dublin	IE_EA_G_008	N/A	Good	Review	Underlying groundwater- body

6.2.1.2 Designated Sites

6.2.1.3 Designated Sites such as European sites- SACs, and SPAs, pNHAs, Ramsar Sites, and UNESCO Sites potentially linked to the Site of the Proposed Development are discussed in this section.

6.2.1.4 European Sites

The following conclusion is extracted from the AA Screening Report accompanying this application under separate cover (Enviroguide, 2025) for both plots (Luttrellstown Gate Phase 2 and St. Mochta's LRD) of the Proposed Development:

"The Proposed Development at Luttrellstown Gate site Plot 1 and St Mochtas Site Plot 2 located at St. Mochtas, Kellystown, Dublin 15 has been assessed considering:

- The nature, size and location of the Proposed Development and possible impacts arising from the construction and/or operational phase.
- The SCI/QIs and conservation objectives of the European sites.
- The potential for in-combination effects arising from other plans and projects.

In conclusion, upon the examination, analysis and evaluation of the relevant information and applying the precautionary principle, it is concluded by the authors of this report that the possibility **may be excluded** that the Proposed Development will have a significant effect on any of the European sites listed below:

- South Dublin Bay SAC (000210),
- South Dublin Bay and River Tolka Estuary SPA (004024)
- North Dublin Bay SAC (000206)
- North Bull Island SPA (004006)
- North-West Irish Sea SPA (004326)
- Rye Water Valley/Cartron SAC (001398)

In carrying out this AA screening, any targeted ecological mitigation measures and/or measures intended or included for the purposes of avoiding adverse effects arising as a result of the Proposed Development on any European site have not been taken into account.

On the basis of the screening exercise carried out above, it can be concluded, on the basis of the best scientific knowledge available and objective information, that the possibility of any significant effects on the above listed European sites, whether arising from the project itself or in combination with other plans and projects, can be excluded in light of the above listed European sites' conservation objectives. Thus, there is **no** requirement to proceed to Stage 2 of the Appropriate Assessment process; and the preparation of a NIS is not required."

As such, European sites are not considered further in this report.

6.2.1.4.1 Proposed Natural Heritage Areas (pNHA)

The Royal Canal (002103) pNHA is of **national importance** and is the closest pNHA to the Site of the Proposed Development, located approximately 40m away from the Site. This is significant enough a distance that impact pathways via land and air pathways are deemed insignificant. Furthermore, there are no water courses present on Site that connect to the Royal Canal Main Line stream that flows in this pNHA, and the existing train line north of the Site will act as a buffer to surface water flow between the Site and the pNHA. While there is a hydrogeological pathway to this pNHA from the Site of the Proposed Development, the embedded mitigations for the Construction Phase of the

Proposed Project will negate any impacts via this pathway. Therefore, it is concluded that impact pathways between the Proposed Development and *Royal Canal* pNHA is considered to be insignificant, with **negligible** level of impact, which at a national level identifies as **slight** impact level to the pNHA.

6.2.1.4.2 Ramsar Sites

The Sandymount Strand/ Tolka Estuary (832) Ramsar site is of international importance and is the closest Ramsar site to the Site of the Proposed Development, located approximately 13km southeast of the Site. The Royal Canal Main Line stream north of the Site flows into this Ramar Site. However, given the lack of hydrological connections between the Site and the stream, the embedded mitigation measures for the Construction Phase of the Proposed Project for hydrogeological pathways to the stream, the dilution effect of the intervening river distance up to the point of discharge into the transitional waterbodies, the tidal nature of the waters near Sandymount Strand/ Tolka Estuary Ramsar site, and the presence of the train line that will act as a buffer to surface water flows from the Site, it can be concluded that impact pathways between the Proposed Development and this Ramsar site is considered to be insignificant, with no change in the level of impact, which at an international level identifies as neutral level of impacts to Sandymount Strand/ Tolka Estuary (832).

6.2.1.4.3 <u>UNESCO Sites</u>

The *Dublin Bay Biosphere* UNESCO site is of **international importance** and is the closest UNESCO site to the Site of the Proposed Development, located approximately 10km east of the Site. The Royal Canal Main Line stream north of the Site discharges into the UNESCO site. However, given the lack of hydrological connections between the Site and the stream, the embedded mitigation measures for the Construction Phase of the Proposed Project for hydrogeological pathways to the stream, the dilution effect of the intervening river distance up to the point of discharge into this site, and the presence the train line that will act as a buffer to surface water flows from the Site, it can be concluded that impact pathways between the Proposed Development and this UNESCO site is considered to be insignificant. Therefore, **no change** in the level of impacts to this UNESCO site is foreseen, which at an international level translates to **neutral** level of impacts to *Dublin Bay Biosphere*.

ENVIRONMENTAL IMPACT ASSESSMENT REPORT KELLYSTOWN




Figure 6.1: Designated Sites located within the Zone of Influence (ZOI) of Plot 1 (Luttrellstown Gate Phase 2)

ENVIRONMENTAL IMPACT ASSESSMENT REPORT KELLYSTOWN



Figure 6.2: Designated Sites located in proximity to Plot 1 (Luttrellstown Gate Phase 2)

6.2.1.5 Habitats

The habitats present within the Site, as recorded in the survey area during the field survey conducted on 27th March 2025, are described in this section and summarised below. Site Photographs of these habitats are included in Appendix 6.2 and a map of the habitats is presented in Figure 6.3.

This Site consists of the following habitats:

- GA1 Improved agricultural grasslands
- WL1 Hedgerows
- ED2 Spoil and Bare Ground

6.2.1.5.1 <u>Improved Agricultural Grassland (GA1)</u>

The majority of the Site is dominated by short, ranked species – poor grassland with evidence of recent grazing activity given their relatively short size. Within this habitat, there are linear stretches of disturbed ground running north to south, likely resulting from past drainage works.

Floral species found in this habitat include the dominant perennial ryegrass (*Lolium perenne*), with scattered populations of spear thistle (*Cirsium vulgare*), hybrid dock (*Rumex sp.*), and creeping buttercup (*Ranunculus repens*). Isolated populations of hogweed (*Heracleum sphondylium*) were recorded, and nettle (*Urtica dioica*) and cleavers (*Galium aparine*) were recorded only along the perimeters of this habitat.

The improved agricultural grassland habitat for this Site has been assigned as **less than local importance**. This habitat is therefore not considered further within this assessment.

6.2.1.5.2 <u>Hedgerows (WL1)</u>

The hedgerow (WL1) habitats were recorded along the perimeter of the Site, where scattered populations of large elder (*Sambucus nigra*) trees were recorded along the northern and southern hedgerows. This habitat was assessed using the methodology outlined by Foulkes et al. (2013)

Floral species found in this habitat were predominantly elder, with scattered distribution of common hawthorn (*Crataegus monogyna*), and blackthorn (*Prunus spinosa*). In some sections of the hedgerow along the northern and southern boundaries, elder was not cut and were allowed to take their arborescent forms, which were identified as large trees along the hedgerows.

At the base of the hedgerows, the grassland habitat transitioned to bramble (*Rubus fructicosus s.*) with patches of nettle, cleavers, and common ivy (*Hedera helix*) among other common tall ruderal and scrub species typically found at field margins and hedgerow bases. Therefore, the hedgerows habitat for this Site has been assigned as **local importance**.

6.2.1.5.3 Spoil and Bare Ground (ED2)

The spoil and bare ground (ED2) habitat was recorded along the southern section of the Site, where construction works as part of a different planning application (Kellystown SHD scheme ABP-312318-21) is currently underway. This habitat was devoid of any floral species, and was identifies due to the presence of spoil and bare ground in this section of the habitat. Therefore, the spoil and bare ground habitat for this Site has been assigned **less than local importance** in terms of ecological importance.



Figure 6.3: Existing habitats recorded at Plot 1 (Luttrellstown Gate Phase 2) as assessed during the Site survey conducted on 27th March 2025

6.2.1.6 Species and Species Groups

6.2.1.6.1 Flora

6.2.1.6.1.1 Rare and Protected Flora

Species records available from the National Biodiversity Data Centre (NBDC) online database for the 10 km grid square (O03), 2km grid squares (O03N, and O03T) and the 1km grid squares (O0537, and O0637) were studied for the presence of rare or protected flora species. The NBDC datasets for the (O0637) 1km grid square yielded no records. This database contained no records of protected flora within the last 20 years, however, several regionally extinct or vulnerable plant species occurred within the 1km grid square (O0537), 2km grid squares (O03N, and O03T), and 10km grid square (O03) are shown in Table 6.4 below (NBDC, 2025).

Table 6.4: Records of Rare or Protected Flora For the Surrounding 10km (O03), 2km (O03N AND O03T), and 1km (O0537) grid squares Associated with the Site from the NBDC

Species	NBDC Grid Square	Date of Last Record	Database	Conservation Status
Common Gromwell (Lithospermum officinale)	O03 (10km)	18/07/2020	Vascular plants: Online Atlas of Vascular Plants 2012 Onwards	Threatened Species: Near threatened
Cornflower (Centaurea	003 (10km)	26/08/2020	Vascular plants: Online Atlas of	Threatened Species:
cyanus)	O03T (2km)		Vascular Plants 2012 Onwards	Waiting list
Fragrant Agrimony	O03 (10km)		Vascular plants:	TI . 16 :
(Agrimonia procera)	O03N (2km)	04/07/2019	Vascular Plants Near threat	Threatened Species: Near threatened
ριουεια	O0537 (1km)		2012 Onwards	
Greater Knapweed	O03 (10km)	26/03/2022	Vascular plants: Online Atlas of	Threatened Species:
(Centaurea scabiosa)	O03N (2km)		26/03/2022 Va	Vascular Plants
,	O0537 (1km)		2012 Onwards	
Green Figwort (Scrophularia umbrosa)	003 (10km)	10/07/2020	Vascular plants: Online Atlas of Vascular Plants 2012 Onwards	Threatened Species: Endangered
Hairy St John's- wort (<i>Hypericum</i>	003 (10km)	22/05/2023	Vascular plants: Online Atlas of Vascular Plants	Protected Species: Flora Protection Order.
hirsutum)			2012 Onwards	Threatened Species: Endangered
Meadow Crane's- bill (<i>Geranium</i> pratense)	O03 (10km)	08/08/2021	Vascular plants: Online Atlas of Vascular Plants 2012 Onwards	Threatened Species: Vulnerable

Pale Flax (Linum bienne)	O03 (10km)	14/07/2021	Vascular plants: Online Atlas of Vascular Plants 2012 Onwards	Threatened Species: Near threatened
Spring Vetch (<i>Vicia</i> lathyroides)	003 (10km)	18/05/2012	Ireland's BioBlitz	Threatened Species: Least concern
Strawberry-tree (Arbutus unedo)	O03 (10km)	26/02/2023	Vascular plants: Online Atlas of Vascular Plants 2012 Onwards	Threatened Species: Near threatened
Yellow Archangel (Lamiastrum galeobdolon)	O03 (10km)	12/05/2018	Vascular plants: Online Atlas of Vascular Plants 2012 Onwards	Threatened Species: Least concern
Yellow Horned- poppy (Glaucium flavum)	O03 (10km)	21/06/2020	Vascular plants: Online Atlas of Vascular Plants 2012 Onwards	Threatened Species: Near threatened

None of the aforementioned protected or rare floral species were recorded on Site during the Site survey conducted on 27th March 2025. Therefore, these species are of **less than local importance** and are not considered further in this report for this Site.

6.2.1.6.1.2 Invasive Species

No invasive floral species were recorded in the (O0637) 1km grid square, and the (O03T) 2km grid squares encompassing the Site of the Proposed Development. However, three high impact and seven medium impact invasive species were recorded within the (O0537) 1km grid square, (O03N) 2km grid square, and (O03) 10km grid square. The details of these species have been listed in Table 6.5 below.

Table 6.5: Records of Invasive Flora for the Surrounding 1km (O0537) grid square, 2km (O03N) grid square, and 10km (O03) grid square Associated with the Site from the NBDC

Species	NBDC Grid Square	Date of Last Record	Database	Legal Status
Three-cornered Garlic (<i>Allium</i>	O0537 (1km)	19/05/2024	Vascular plants: Online Atlas of	Medium Impact Invasive Species
triquetrum)	O03N (2km)	13/03/2024	Vascular Plants 2012 Onwards	Regulation S.I. 477 (Ireland)
Douglas Fir (Pseudotsuga menziesii)	O03N (2km)	22/08/2005	Species Data from the National Vegetation Database	Medium Impact Invasive Species
Cherry Laurel (Prunus laurocerasus)	O03N (2km)	22/08/2005	Species Data from the National Vegetation Database	High Impact Invasive Species

False-acacia (Robinia pseudoacacia)	O03N (2km)	22/08/2005	Species Data from the National Vegetation Database	Medium Impact Invasive Species
Himalayan Honeysuckle (<i>Leycesteria</i> <i>formosa</i>)	O03N (2km)	22/08/2005	Species Data from the National Vegetation Database	Medium Impact Invasive Species
Rhododendron ponticum	O03N (2km)	22/08/2005	Species Data from the National Vegetation Database	High Impact Invasive Species Regulation S.I. 477 (Ireland)
Sycamore (Acer pseudoplatanus)	O03N (2km)	22/08/2005	Species Data from the National Vegetation Database	Medium Impact Invasive Species
Traveller's-joy (Clematis vitalba)	O03N (2km)	22/08/2005	Species Data from the National Vegetation Database	Medium Impact Invasive Species
Butterfly-bush (<i>Buddleja davidii</i>)	O03	26/02/2023	Vascular plants: Online Atlas of Vascular Plants 2012 Onwards	Medium Impact Invasive Species
Nuttall's Waterweed (Elodea nuttallii)	O03	18/07/2020	Vascular plants: Online Atlas of Vascular Plants 2012 Onwards	High Impact Invasive Species Regulation S.I. 477 (Ireland)

None of the aforementioned invasive floral species were recorded on Site during the Site survey conducted on 27th March 2025. Therefore, these species are of **less than local importance** and are not considered further in this report for this Site.

6.2.1.6.2 <u>Bats</u>

6.2.1.6.2.1 Desk Study Results

Seven bat species were recorded in the 2km (O03N, and O03T), and 1km (O0637, and O0537) grid squares encompassing the Site. These species have been listed in Table 6.6 below. One additional bat species, whiskered bat (*Myotis mystacinus*) was recorded in the 10km (O03) grid square encompassing the Site.

Table 6.6: Records of Bat Species for the Surrounding grid squares associated with the Site from the NBDC

Species	NBDC Grid Square	Date of Last Record	Database	Legal Status
Common	O0637 (1km)	02/05/2022	National Bat Database of	EU Habitats Directive - Annex
Pipistrelle (<i>Pipistrellus</i>	O0537 (1km)	, , ,	Ireland	IV

pipistrellus sensu stricto)	O03N (2km)	_		Wildlife Act 1976 (as amended)
_	O031 (2km)	15/08/2023		
	. ,	15/08/2023		
	O0637 (1km)			
Daubenton's Bat	O0537 (1km)	02/05/2022	National Bat Database of	EU Habitats Directive - Annex
(Myotis daubentonii)	O03N (2km)		Ireland	IV Wildlife Act 1976
	O03T (2km)			(as amended)
	O03 (10km)	03/05/2022		
	O0637 (1km)	15/08/2008		EU Habitats
Lesser Noctule	00537 (1km)		National Bat	Directive - Annex
(Nyctalus leisleri)	O03N (2km)	02/05/2022	Database of Ireland	IV Wildlife Act 1976
	O03T (2km)			(as amended)
	003 (10km)	15/08/2023		
	O0637 (1km)	02/05/2022	National Bat Database of Ireland	EU Habitats
Soprano Pipistrelle	O0537 (1km)			Directive - Annex
(Pipistrellus pygmaeus)	O03N (2km)			IV Wildlife Act 1976
	O03T (2km)			(as amended)
	O03 (10km)	15/08/2023		
	O0537 (1km)		National Bat Database of	EU Habitats
Brown Long-eared Bat (<i>Plecotus</i>	O03N (2km)	02/05/2022		Directive - Annex IV
auritus)	O03T (2km)		Ireland	Wildlife Act 1976
	O03 (10km)			(as amended)
Nathusius's	O0537 (1km)			EU Habitats
Pipistrelle (Pipistrellus	O03N (2km)	02/05/2022	National Bat Database of	Directive - Annex IV
nathusii)	O03T (2km)	_	Ireland	Wildlife Act 1976
	003 (10km)	1		(as amended)
Natterer's Bat	O03N (2km)	10/09/2005	National Bat Database of	EU Habitats Directive - Annex
(Myotis nattereri)	O03 (10km)	30/09/2008	Ireland	IV Wildlife Act 1976 (as amended)

Whiskered Bat (Myotis mystacinus)	003 (10km)	03/09/2005	National Bat Database of Ireland	EU Habitats Directive - Annex IV Wildlife Act 1976 (as amended)
---	------------	------------	--	---

The Proposed Development (indicated in the black box in Figure 6.4 below) is located in an area with an overall medium - high (35.44) suitability for bats in general. The suitability index for specific bat species is presented in Table 6.7. The landscape suitability index is high for five species of bats, namely soprano Pipistrelle (*Pipistrellus pygmaeus*), brown long-eared bat (*Plecotus auritus*), common pipistrelle (*Pipistrellus pipistrellus*), Leisler's bat (*Nyctalus leislerii*), and natterer's bat (*Myotis nattereri*). The landscape suitability index is medium – high for two species of bat, namely whiskered bat (*Myotis mystacinus*), and Daubenton's bat (*Myotis daubentonii*).

Table 6.7: Landscape Suitability Index For Individual Bat Species Within The 2km Grid Square (Source: NBDC). Those Species That Have Been Recorded In The NBDC Database Within The O03 10km Grid Square Are Highlighted In Green

Bat Species	Suitability Index (2km Grid Square)
Soprano pipistrelle (Pipistrellus pygmaeus)	43 (High)
Brown Longed-eared bat (Plecotus auritus)	50 (High)
Common pipistrelle (Pipistrellus pipistrellus)	50 (High)
Lesser horseshoe bat (Rhinolophus hipposideros)	0 (Low)
Leisler's bat (Nyctalus leisleri)	51 (High)
Whiskered bat (Myotis mystacinus)	33 (Medium - High)
Daubenton's bat (Myotis daubentonii)	33 (Medium - High)
Nathusius' pipistrelle (Pipistrellus nathusii)	18 (Low - Medium)
Natterer's bat (Myotis nattereri)	41 (High)
36.444402 - 58.555599 28.111100 - 36.444401 21.333301 - 28.111099 13.000001 - 21.333300 0.000000 - 13.000000	L100 m Scale: 1:5000 - Resolution: 100m 705456, 737625

Figure 6.4: bat landscape suitability model (all bats) surrounding Plot 1 (Luttrellstown Gate Phase 2) indicated by the black box (NBDC, 2025)

STEPHEN LITTLE & ASSOCIATES MAY 2025

6.2.1.6.2.2 Field Survey Results

6.2.1.6.2.2.1 Bat Roost Assessment and Habitat Suitability

During the Site visit on 27th March 2025, a Preliminary Bat Roost Assessment (PBRA) was conducted on all trees within the Site. No buildings occur within the Site of the Proposed Development. The ground-based PBRA found that the trees present at the Site fall under the BCT categories of NONE or PRF-I, therefore the Site holds limited potential to support singular opportunistic bat roosts.

The linear hedgerows feature along the boundaries of the Site were assessed as providing 'Moderate' habitat suitability for foraging and commuting bats.

The Site of the Proposed Development is not exposed to high light levels given the lack of residential housing near the Site. The trainline to the north, agricultural fields to the west, and construction works to the south of the Site expose the Site to very low ambient light levels along these areas. However, the majority of the Site is likely to be undisturbed by artificial lighting and is well connected to the surrounding landscape, which consists of agricultural fields to the east, and linear green corridors along the trainline to the north. Therefore, the Site is of **less than local importance** for roosting bats but is of **local importance** to commuting and foraging bats.

6.2.1.6.2.2.2 Bat Activity Transect Survey

As per the best standard practice guidelines and the assessment of PBRA assessment conducted for the Site, two seasonal bat activity transect surveys have been recommended, with one survey carried out in May) for Spring), and one survey to be carried out between June and August (for Summer).

6.2.1.6.3 Birds

6.2.1.6.3.1 Desk Study Results

A total of 104 bird species have been recorded within the (O03) 10km grid square, (O03T, and O03N) 2km grid square, and (O0637) 1km grid squares. Of these, 17 are red listed bird species, 32 are amber listed bird species, and the remaining are green listed bird species (and some bird species with no classification) as identified on the Birds of Conservational Concern in Ireland (BoCCI) (Gilbert er al. 2021). Details of amber and red listed species are detailed in **Error! Reference source not found.** in Appendix 6.1.

6.2.1.6.3.2 Field Survey Results

6.2.1.6.3.2.1 Bird Scoping Survey

A total of five bird species were observed at the Site during the walkover survey on 27th March 2025, where none of the species recorded were red or amber listed species as per the Birds of Conservation Concern in Ireland 2020-2026 (Gilbert et al., 2021). All of the bird species recorded are green listed species and have been listed in Table 6.8 below. Therefore, the Site is of **local importance** to bird species.

Table 6.8: Bird Species recorded during walkover survey on 27th March 2025

Species	BoCCI Status
Robin (Erithacus rubecula)	Green
Magpie (<i>Pica pica</i>)	Green
Hooded Crow (Corvus corone)	Green
Wood pigeon (Columba palumbus)	Green
Dunnock (Prunella modularis)	Green

In addition to the list of bird species observed at the Site, two disused nests were found within the large elder trees along the southern hedgerow, which indicated that the Site was previously used by breeding tree-nesting birds.

6.2.1.6.3.2.2 Breeding Bird Surveys

As per the best standard practice guidelines and habitats assessed on the Site, one seasonal bird breeding survey has been recommended, which can take place between the months of May to early July (within the breeding bird season).

6.2.1.6.4 Mammals (excl. bats)

6.2.1.6.4.1 Desk Study Results

A total of 19 mammals were recorded within the 10km (O03), 2km (O03N and O03T), and 1km (O0637 and O0537) grid squares. Off these, eleven species are native terrestrial mammals, with seven of these species afforded legal protection under the Wildlife (Amendment) Act, 2000, namely badger (*Meles meles*), otter (*Lutra lutra*), pine marten (*Martes martes*), red deer (*Cervus elaphus*), hedgehog (*Erinaceus europaeus*), red squirrel (*Sciurus vulgaris*), and Eurasian pygmy shrew (*Sorex minutus*)

The remaining eight species are considered invasive and/or non-native, namely brown rat (*Rattus norvegicus*), rabbit (*Oryctolagus cuniculus*), brown rat (*Rattus norvegicus*), American mink (*Mustela vison*), eastern grey squirrel (*Sciurus carolinensis*), fallow deer (*Dama dama*), house mouse (*Mus musculus*), Siberian chipmunk (*Tamias sibiricus*), and sika deer (*Cervus nippon*). These species have been recorded across the 10km (O03) grid square encompassing the Site of the Proposed Development.

Table 6.9: Records of mammal species (excl. bats) for the surrounding grid squares associated with the Site from the NBDC

Species	Grid Square	Date of Last Record	Database	Designation
		Native Species		
Eurasian Badger	O03 (10km)	08/04/2023	Mammals of Ireland 2016-2025	Wildlife (Amendment) Act
(Meles meles)	O03N (2km)	25/07/2010	Road Kill Survey	2000 Berne Convention
O0537 (1km)		,	Appendix III	
Eurasian Pygmy Shrew (<i>Sorex</i> <i>minutus</i>)	O03 (10km)	03/10/2015	Atlas of Mammals in Ireland 2010- 2015	Wildlife (Amendment) Act 2000
Eurasian Red Squirrel (<i>Sciurus</i> <i>vulgaris</i>)	O03 (10km)	24/01/2015	Atlas of Mammals in Ireland 2010- 2015	Wildlife (Amendment) Act 2000
European Otter 003 (10km		06/12/2018	Mammals of	
(Lutra lutra)	O03N (2km)	15/05/2016	Ireland 2016-2025	

	O03T (2km)	20/08/2014	Atlas of Mammals in Ireland 2010- 2015	Wildlife (Amendment) Act	
	O0537 (1km)	15/05/2016	Mammals of Ireland 2016-2025	2000	
Irish Hare (Lepus timidus subsp. hibernicus)	O03 (10km)	23/02/2020	Mammals of Ireland 2016-2025 N/A		
Irish Stoat (Mustela erminea subsp. hibernica)	O03 (10km)	14/04/2024	Irish Stoats of Ireland	N/A	
	O03 (10km)	21/05/2021		Wildlife	
Pine Marten (Martes martes)	O03N (2km)	04/06/2020	Mammals of Ireland 2016-2025	(Amendment) Act	
,	O03T (2km)	17/08/2019	_	2000	
Red Deer (<i>Cervus</i> elaphus)	O03 (10km)	31/12/2008	Deer of Ireland Database	Wildlife (Amendment) Act 2000	
	O03 (10km)	21/01/2023	Mammals of Ireland 2016-2025		
Red Fox (Vulpes	O03N (2km)	17/04/2007	Road Kill Survey	N/A	
vulpes)	O03T (2km)	28/07/2012	Atlas of Mammals in Ireland 2010- 2015	IV/A	
	O03 (10km)	07/12/2023			
West European	O03N (2km)	09/04/2021	Hedgehogs of	Wildlife	
Hedgehog (<i>Erinaceus</i>	O03T (2km)	12/05/2021	Ireland	(Amendment) Act	
europaeus)	00637 (1km)	05/05/2021		2000	
	00537 (1km)	16/09/2011	Road Kill Survey		
Wood Mouse (Apodemus sylvaticus)	O03 (10km)	20/05/2011	Ireland's BioBlitz	N/A	
	Non-	native and Invasive S	pecies		
American Mink	O03 (10km)	02/08/2018	Mammals of Ireland 2016-2025	High Impact Invasive Species	
(Mustela vison)	O03N (2km)	27/03/2007	Road Kill Survey	Regulation S.I. 477 (Ireland)	
Brown Rat (Rattus norvegicus)	O03 (10km)	20/11/2015	Atlas of Mammals in Ireland 2010- 2015	High Impact Invasive Species	

	O03T (2km)	27/09/2014	Atlas of Mammals in Ireland 2010- 2015	Regulation S.I. 477 (Ireland)	
	O03 (10km)	17/11/2022	Mammals of Ireland 2016-2025		
Eastern Grey	O03N (2km)	04/10/2012	Atlas of Mammals in Ireland 2010- 2015	High Impact Invasive Species	
Squirrel (Sciurus carolinensis)	O03T (2km)	23/06/2022	Mammals of Ireland 2016-2025	Regulation S.I. 477 (Ireland)	
	00637 (1km)	25/05/2008	Road Kill Survey	(ireland)	
	00537 (1km)	04/10/2012	Atlas of Mammals in Ireland 2010- 2015		
	O03 (10km)	31/03/2023	Mammals of Ireland 2016-2025		
European Rabbit (<i>Oryctolagus</i>	O03N (2km)	06/08/2010	Road Kill Survey	Medium Impact Invasive Species	
cuniculus)	O03T (2km)	21/01/2023	Mammals of Ireland 2016-2025		
	00537 (1km)	06/08/2010	Road Kill Survey		
Fallow Deer (<i>Dama</i> dama)	O03 (10km)	19/07/2018	Mammals of Ireland 2016-2025	High Impact Invasive Species Regulation S.I. 477 (Ireland)	
House Mouse (Mus musculus)	O03 (10km)	01/11/2012	Atlas of Mammals in Ireland 2010- 2015	High Impact Invasive Species	
Siberian Chipmunk (Tamias sibiricus)	O03 (10km)	15/07/2011	National Invasive Species Database	High Impact Invasive Species Regulation S.I. 477 (Ireland)	
Sika Deer (<i>Cervus</i> nippon)	O03 (10km)	31/12/2008	Deer of Ireland Database	High Impact Invasive Species Regulation S.I. 477 (Ireland)	

6.2.1.6.4.2 Field Survey Results

6.2.1.6.4.2.1 <u>Large Mammals</u>

During the site walkover survey conducted on 27th March 2025, no signs of large mammal species at the Site of the Proposed Development were recorded.

Badger

No direct sightings, badger setts, footprints, latrines, hairs, feeding activity, snuffle holes or badger scat was recorded at the Site of the Proposed Development. This indicated that badgers do not

regularly utilise the Site. Furthermore, while there are green corridors between the Site and the agricultural fields to the west via the green corridor along the northern boundary of the Site, the absence of field signs suggest that the Site is not currently being used by badgers., either as commuting route or for sett establishment. Therefore, Plot 1 (Luttrellstown Gate Phase 2) Site of the Proposed Development is unlikely to be of significant importance to badger population in the greater area and is of lesser than local importance.

Otter

No signs of otter activity, such as direct sightings, spraints, holts, couches, footprints or feeding remains were recorded at the Site of the Proposed Development. This indicated that otters are not currently using the Site for activities such as foraging, commuting, or resting. While there is an existing stagnant water pond at the northwest section of the Site, there is no water course connecting this pond with the nearby Royal Canal where otters have been listed as QI. Given the polluted nature of the pond and lack of connectivity to the Royal Canal stream flowing north of the Site, it is considered that Plot 1 (Luttrellstown Gate Phase 2) Site of the Proposed Development is unlikely to be of significant importance to otter populations in the greater area and is of lesser than local importance.

Red Deer

During the Site survey, no tracks, droppings, feeding signs, or sightings was recorded at the Site of the Proposed Development. This indicated that red deer do not regularly utilise the Site. Furthermore, while there are green corridors connecting the Site to larger green spaces to the east of the Site, the lack of field signs indicate that the Site does not currently form part of any known range of red deer. Therefore, it is considered that the Site of the Proposed Development is unlikely to be of significant importance to red deer populations in the greater area and is of **lesser than local importance**.

Fox

No evidence of fox activity, such as tracks, scat, dens or remains of prey were recorded at the Site of the Proposed Development. Although foxes are common and widespread across Ireland, the absence of field signs suggested that the Site is not of significant importance to local fox populations in the greater area, and the Site itself is of **less than local importance** to this species.

Other mammals

Due to the limited number of large trees with tree hollows or crevices, lack of wooded habitat and lack of ecological corridors for larger mammal species, it is unlikely pine marten, or red squirrel would utilise the Site. Therefore, the Site of the Proposed Development is of **less than local importance** for these species.

6.2.1.6.4.2.2 Smaller Mammals

Suitable habitats for smaller mammal species, such as hedgehogs, hare, wood mouse, and pygmy shrew was recorded along the hedgerows bordering the Site, along with the grassland habitat on Site. The western field parcel, just outside the Site boundary contains a scattered piles of logs and branches, which are suitable hibernacula/refuge for small mammals. However, burrows were not recorded across the Site, indicating the absence of the aforementioned species during the survey.

Although no direct evidence of hedgehogs, hare, wood mouse and pygmy shrew was recorded during the Site walkover, the range of habitats present within the Site, including the hedgerows and grassland habitats are considered to be suitable habitat for these species. Given the timid, nocturnal or cyptic behaviour of some of the aforementioned species, it can be considered that these species

may utilise the Site in the future. Therefore, it can be concluded that the Site has the potential to provide suitable commuting, foraging and resting habitats for smaller mammals, which can be significantly impacted during the Construction and/or Operational Phases of the Proposed Development in the absence of mitigation. For these reasons, the Site of the Proposed Project has been assigned **local level of importance**.

6.2.1.6.5 Amphibians

Both common frog (*Rana temporaria*) and smooth newt have (*Lissotriton vulgaris*) been recorded in the 10km (O03) and 2km (O03T) grid squares encompassing the Site of the Proposed Development.

Table 6.10: Records of amphibians for the surrounding grid squares associated with the Site from the NBDC

Species	Grid Square	Date of Last Record	Database	Designation
Common Frog	O03T (2km)	25/02/2023	Amphibians and	Wildlife (Amendment) Act
(Rana temporaria)	(Rana temporaria) 003 (10km)		reptiles of Ireland	2000
Smooth Newt (Lissotriton vulgaris)	003 (10km)	05/04/2023	Amphibians and reptiles of Ireland	Wildlife (Amendment) Act 2000

During the walkover survey on 27th March 2025, habitats on Site were checked for signs of amphibians. No ponds or other areas of standing water were recorded at the Site. However, a stagnant and polluted water pond was located outside the northwest section of the Site, which is a suitable habitat for amphibians. However, no common frogs or smooth newts or spawns of these species were recorded during the walkover survey, and given the extremely polluted nature of water, it is unlikely for amphibians to occur in the pond. For these reasons, the Site of the Proposed Development has been assigned **less than local level of importance**.

6.2.1.6.6 Reptiles

No records of common lizard (*Zootoca vivipara*) exist for the relevant 10km (O03), 2km (O03N and O03T), and 1km (O0537 and O0637) grid squares encompassing the Site of the Proposed Development. However, there is some suitable habitat for this species within the Site of the Proposed Development along the hedgerow habitat. As no targeted surveys for common lizard were carried out, it is assumed under the precautionary principle that a locally important population of this species may be present at the Site. Therefore, the Site of the Proposed Development has been identified as **local importance** for common lizards.

Within the 10km (O03), 2km (003T), and 1km (O0637) grid squares, two invasive reptile species have been listed, namely red-eared terrapin (*Trachemys scripta*), and yellow-bellied slider (*Trachemys scripta scripta*). Whiles there are suitable habitats for these species on Site of the Proposed Development, these species were not recorded during the walkover survey.

6.2.1.6.7 Fish and other Aquatic Species

While protected species such as European eel (*Anguilla anguilla*), and grey seals (*Halichoerus grypus*) have been recorded within the 10km (O03) grid square encompassing the Site of the Proposed Development, there are no waterbodies within the Site of the Proposed Development that could support notable fish or aquatic species.

The Site drainage network during the Operational Phase of the Development does not connect to the Royal Canal that flows north of the Site. Therefore, fish and other aquatic species are not a

consideration during this phase of the Proposed Development, and the Site is identified as **less than local importance** for fish and other aquatic species.

6.2.1.6.8 Marsh Fritillary

The marsh fritillary (*Euphydryas aurinia*) butterfly is the only insect in Ireland that is listed on Annex II of the Habitats Directive, which makes it the only insect protected by law in Ireland. There are no records of marsh fritillary from the last five years within the 10km (O030) grid square which encompass the Proposed Development. No individuals of this species or it's associated food plant; devil's bit scabious (*Succisa pratensis*), were recorded during the walkover survey on 27th March 2025. It should be noted that devil's bit scabious is an autumn flowering plant and as such may have been missed during the surveys. Additionally, the recommended survey period for marsh fritillary is in September and October when the caterpillars can be found within silken webs on the leaves of the foodplant. The majority of the Site is improved grassland which is not considered likely to support devil's bit scabious or the marsh fritillary. Therefore, the Site of the Proposed Development is identified as **less than local importance** for marsh fritillary.

6.2.1.6.9 Other Invertebrates

6.2.1.6.9.1 Desk Study Results

Eleven of the invertebrate species were recorded within the 10km (O03), 2km (O03T), and 1km (O0637) encompassing the Site of the Proposed Development. These species are not protected, however are listed as 'Endangered', 'Near Threatened', 'Vulnerable' or 'Data deficient' Conservation status in Ireland.

Table 6.11: Records of rare and invasive invertebrates for the surrounding grid squares associated with the Site from the NDBC

Species	Grid Square	Date of Last Record Database		Conservation Status
		Rare Species		
Andrena (Andrena) fucata	O03 (10km)	31/05/2008	Bees of Ireland	Threatened Species: Near threatened
Andrena (Leucandrena) barbilabris	O03 (10km)	26/04/2022	Bees of Ireland	Threatened Species: Near threatened
Andrena (Melandrena) nigroaenea	O03 (10km)	02/04/2021	Bees of Ireland	Threatened Species: Vulnerable
Andrena (Taeniandrena) wilkella	003 (10km)	31/05/2008	Bees of Ireland	Threatened Species: Data deficient
Gipsy Cuckoo Bee (Bombus (Psithyrus) bohemicus)	O03 (10km)	29/05/2023	Bees of Ireland	Threatened Species: Near threatened
	O03 (10km)	08/05/2023	Bees of Ireland	
	O03T (2km)	25, 35, 252		

Gooden's Nomad Bee (Nomada goodeniana)	O0637 (1km)			Threatened Species: Endangered
Halictus (Seladonia) tumulorum	O03 (10km)	30/07/2008	Bees of Ireland	Threatened Species: Near threatened
Large Red Tailed Bumble Bee	O03 (10km)	16/05/2024		Threatened
(Bombus	O03T (2km)	17/04/2023	Bees of Ireland	Species: Near
(Melanobombus) lapidarius)	O0637 (1km)	27/07/2012		threatened
Megachile (Delomegachile) willughbiella	O03 (10km)	17/07/2021	Bees of Ireland	Threatened Species: Near threatened
Megachile (Megachile) centuncularis	O03 (10km)	22/06/2021	Bees of Ireland	Threatened Species: Near threatened
Moss Carder-bee (Bombus (Thoracombus) muscorum))	O03 (10km)	06/05/2021	Bees of Ireland	Threatened Species: Near threatened
		Invasive Species		
Harlequin Ladybird	O0637 (1km)	02/09/2024		High Impact Invasive Species
(Harmonia axyridis)	O03T (2km)]	Ladybirds of Ireland	Regulation S.I. 477
ихупиіз	O03N (2km)	15/08/2024		(Ireland)

6.2.1.6.9.2 Field Survey Results

During the walkover survey conducted on 27th March 2025, none of the aforementioned rare invertebrate species were recorded. Therefore, the Site of the Proposed Development is identified as **less than local importance** to invertebrate species.

6.2.1.6.10 Protected and/or Notable Species Unlikely to Occur at the Site

Other notable and/or rare species and species listed on Annex IV of the Habitats Directive that were considered but that are unlikely to occur at the Site has been included in Table 6.12 below. The Site of the Proposed Development for these species has been identified as **less than local importance** for these species.

Table 6.12: Protected and/or notable species unlikely to occur at the Site and the reason for exclusion from assessment

Species Reason for exclusion from assessment	
Flo	ora
Marsh Saxifrage (Saxifraga hirculus)	Known populations only in Co. Mayo.

Killarney Fern (<i>Vandenboschia speciosa</i>)	Nearest known populations in Co. Wicklow, not recorded at the Site, no suitably sheltered and moist habitats available.
Slender Naiad (<i>Najas flexilis</i>)	A clear water, lowland lake species. No suitable habitat available at the Site.
Fa	una
White-clawed Crayfish (Austropotamobius pallipes)	Not present in the Liffey, adjacent ditches and streams not considered suitable for this species due to low quality.
Freshwater Pearl Mussel (<i>Margaritifera</i> <i>margaritifera</i>)	Nearest known records from the Barrow catchment to the west of the Site, no hydrological connection to this catchment. Liffey is not listed as a <i>M. margaritifera</i> sensitive area.
Natterjack Toad (<i>Epidalea calamita</i>)	Distribution restricted to few coastal sites.
Kerry Slug (Geomalacus maculosus)	Distribution restricted to south and west of Ireland

6.2.2 Proposed Development - Plot 2 (St. Mochta's LRD).

6.2.2.1 Geology, Hydrogeology, and Geology

The Proposed Development – Plot 2 (St. Mochta's LRD) is located within the Liffey_SC_100 sub catchment within the Liffey and Dublin Bay catchment. The nearest mapped watercourse to Plot 2, namely Royal Canal Main Line (Liffey and Dublin Bay) (IE_09_AWB_RCMLE) stream is located approximately 35m to the north (EPA, 2025). This watercourse is classified as being of 'Good' qualify for the survey period 2016 – 2021. There are no Q-values available for along the length of this stream. The Royal Canal Main Line (Liffey and Dublin Bay) flows east then southeast for approximately 12km from the Proposed Development, before discharging into the Liffey Estuary Lower (IE_EA_090_0300) transitional waterbody. This then ultimately flows into the Dublin Bay (IE_EA_090_0000) coastal waterbody, which is located 16.4km downstream of the Proposed Project.

The groundwater body underlying the Site is the Dublin (IE_EA_G_008), which is classed as being of 'Good' water quality for the 2016 – 2021 survey period. The bedrock aquifer identified beneath the Site is mapped as "Locally Important Aquifer - Bedrock which is Moderately Productive only in Local Zones" (LI), with a small section at the southwest section of the Site classed as "Poor Aquifer - Bedrock which is Generally Unproductive except for Local Zones" (PI). The Groundwater Vulnerability Rating assigned to groundwater beneath this plot of the Site is mapped as "Extreme" (E) for the predominant area, and "Rock at or near Surface or Karst" (X) for a small section along the southwest boundary of the Site (GSI, 2025).

The soil beneath the Site comprises "Fine loamy drift with limestones". The quaternary sediments beneath the Site are mapped as "Till derived from limestones" (TLs) while the subsoils beneath the Site are mapped as "Limestone till (Carboniferous)" (TLs) for the predominat area, with a small section along the eastern boundary of the Site classed as "Bedrock at surface" (RcK) (GSI, 2025)

The Waterbody Status for river, groundwater, transitional and coastal water bodies relevant to the Site as recorded by the EPA (2025) in accordance with European Communities (Water Policy) Regulations 2003 (SI no. 722/2003) are provided in Table 6.13.

Table 6.13: WFD Risk and Waterbody Status

Waterbody Name	Water body; EU code	Distance from Site (km)	WFD water body status (2016-2021)	WFD 3 rd cycle Risk Status	Hydraulic Connection to the Site
		Surface Water B	Bodies		
Royal Canal Main Line (Liffey and Dublin Bay)	IE_09_AWB_RCMLE	35m N	Good	Review	None
	Т	ransitional Wate	r Bodies		
Liffey Estuary Lower	IE_EA_090_0300	12km SE	Moderate	At Risk	Downstream
		Coastal Water B	Bodies		
Dublin Bay	IE_EA_090_0000	16.4km E	Good	Not at Risk	Downstream
	Groundwater Bodies				
Dublin	IE_EA_G_008	N/A	Good	Review	Underlying groundwater- body

6.2.2.2 Designated Sites

Designated Sites such as European sites- Special Areas of Conservation (SAC), and Special Protection Area (SPA), proposed Natural Heritage Areas (pNHAs), Ramsar Sites, and United Nations Educational, Scientific and Cultural Organization (UNESCO) Sites potentially linked to the Site of the Proposed Development are discussed in this section

6.2.2.2.1 European Sites

The following conclusion is extracted from the AA Screening Report accompanying this application under separate cover (Enviroguide, 2025) for both plots (Luttrellstown Gate Phase 2 and St. Mochta's LRD) of the Proposed Development and is included in section 6.2.1.4 of this report.

As such, European sites are not considered further in this report.

6.2.2.2.2 Proposed Natural Heritage Areas (pNHA)

The Royal Canal (002103) pNHA is of national importance and is the closest pNHA to the Site of the Proposed Development, located approximately 17m away from the Site. This is significant enough a distance that impact pathways via land but not air pathways are deemed insignificant. However, there are no water courses present on Site that connect to the Royal Canal Main Line stream that flows in this pNHA, and the existing train line north of the Site will act as a buffer to surface water flow between the Site and the pNHA. While there is a hydrogeological pathway to this pNHA from the Site of the Proposed Development, the embedded mitigations for the Construction Phase of the Proposed Project will negate any impacts via this pathway. Furthermore, impacts via air pathways such as noise disturbances will not impact QIs of Royal Canal pNHA such as otters (Lutra lutra) due to their acclimatisation with high levels of noise generated from the existing carriageway along the eastern boundary of the Site, and the train line beyond the northern boundary. Therefore, it is concluded that impact pathways between the Proposed Development and Royal Canal pNHA is considered to be insignificant, with negligible level of impact, which at a national level identifies as slight impact levels to the pNHA.

6.2.2.2.3 Ramsar Sites

The Sandymount Strand/ Tolka Estuary (832) Ramsar site is of international importance and is the closest Ramsar site to the Site of the Proposed Development, located approximately 12.3km southeast of the Site. The Royal Canal Main Line stream north of the Site flows into this Ramar Site. However, given the lack of hydrological connections between the Site and the stream, the embedded mitigation measures for the Construction Phase of the Proposed Project for hydrogeological pathways to the stream, the dilution effect of the intervening river distance up to the point of discharge into the transitional waterbodies, the tidal nature of the waters near Sandymount Strand/ Tolka Estuary Ramsar site, and the presence of the train line that will act as a buffer to surface water flows from the Site, it can be concluded that impact pathways between the Proposed Development and this Ramsar site is considered to be insignificant, with no change in the level of impact, which at an international level identifies as neutral level of impacts to Sandymount Strand/ Tolka Estuary (832).

6.2.2.2.4 <u>UNESCO Sites</u>

The *Dublin Bay Biosphere* UNESCO site is of **international importance** and is the closest UNESCO site to the Site of the Proposed Development, located approximately 9.7km east of the Site. The Royal Canal Main Line stream north of the Site discharges into the UNESCO site. However, given the lack of hydrological connections between the Site and the stream, the embedded mitigation measures for the Construction Phase of the Proposed Project for hydrogeological pathways to the stream, the dilution effect of the intervening river distance up to the point of discharge into this site, and the

presence the train line that will act as a buffer to surface water flows from the Site, it can be concluded that impact pathways between the Proposed Development and this UNESCO site is considered to be insignificant. Therefore, **no change** in the level of impacts to this UNESCO site is foreseen, which at an international level translates to **neutral** level of impacts to *Dublin Bay Biosphere*.

ENVIRONMENTAL IMPACT ASSESSMENT REPORT KELLYSTOWN




Figure 6.5: Designated sites located within the Zone of Influence (ZOI) of Plot 2 (St. Mochta's LRD)

ENVIRONMENTAL IMPACT ASSESSMENT REPORT KELLYSTOWN




Figure 6.6: Designated Sites located in proximity to Plot 2 (St. Mochta's LRD))

6.2.2.3 Habitats

The habitats present within the Site, as recorded in the survey area during the field survey conducted on 27th March 2025, are described in this section and summarised below. Site Photographs of these habitats are included in Appendix 6.2 and a map of the habitats is presented in Figure 6.7.

This Site consists of the following habitats:

- BL3 Buildings and artificial surfaces
- WL1 Hedgerow
- BC4 Flower beds and borders
- WL2 Treeline
- GS2 Dry meadows and grassy verges
- MWD1 (Mixed) broadleaved woodlands
- GA2 Amenity grassland
- ED2 Spoil and bare ground
- ED3 Recolonising bare ground

6.2.2.3.1 Buildings and artificial surfaces (BL3)

The buildings and artificial surfaces (BL3) habitats were recorded at the western access gate of the Site of the Proposed Development. This habitat was devoid of any floral species, and was identifies due to the presence of buildings at the western boundary of the Site, and the concrete paved surfaces around these structures. Therefore, the buildings and artificial surfaces habitat for this Site has been assigned **less than local importance** in terms of ecological importance.

6.2.2.3.2 Amenity Grassland (GA2)

The amenity grassland (GA2) habitat was the most dominant habitat recorded at the Site of the Proposed Development. This habitat was dominated by perennial ryegrass (*Lolium perenne*) and was used for recreational activities such as soccer pitches. The presence of short grasses in this habitat indicated regular mowing regimes and maintenance.

There were no floral species recorded within this habitat, however, species such as cleavers (*Galium aparine*), and dandelions (*Taraxacum vulgaria*) were observed along the peripheral extents of the habitat where the grasslands were less managed. Therefore, the amenity grassland habitat for this Site has been assigned **less than local importance**.

6.2.2.3.3 <u>Hedgerow (WL1)</u>

Three areas of the hedgerows (WL1) habitat were recorded at the Site of the Proposed Development. Along the western boundary, hedgerows consisted of elder (Sambucus nigra), bramble (Rubus fructicosus s), and common ivy (Hedera helix), with some large elder trees located along the hedgerow. Along the northern boundary of the Site, floral species such as elder, bramble and common ivy were recorded. Invasive butterfly-bush (Buddleja davidii) were also recorded along this hedgerow, where their adbundance increased exponentially at the eastern extent of the habitat. The final stretch of hedgerow was recorded east of the GA2 habitat, where floral species such as elder, blackthorn (Prunus spinosa), bramble, birch (Betula sp.) and yulan magnolia (Magnolia denudata) were recorded. Along this stretch of hedgerows, elder and birch were not cut and were allowed to take their arborescent forms, which were identified as large trees along the hedgerows.

At the base of the hedgerows, the amenity grasslands (GA2) and recolonising bare ground (ED3) habitats transitioned to winter heliotrope (*Petasites pyrenaicus*), mad woman's milk (*Euphorbia helioscopia*), bramble, cleavers, nettle (*Urtica dioica*), dandelion, and common ivy among other common ruderal and scrub species typically found at field margins and hedgerow based. Therefore, the hedgerows habitat for this Site has been identified as of **local importance**.

6.2.2.3.4 Flower beds and borders (BC4)

The flower beds and borders is a small habitat that was recorded at the western access gate to the Site of the Proposed Development. This habitat was restricted in its extent and comprised of ornamental floral species such as *Veronica sp.*, Japanese skimmia (*Skimmia japonica*), Indian cluster berry (*Lonicera ligustrina* Wall), kohuhu (*Pittosporum tenuifolium*), amongst other common species such as daffodil (*Narcissus pseudonarcissus L.*), dandelion, and winter heliotrope. Therefore, the flower beds and border habitat for this Site has been assigned as **less than local importance**.

6.2.2.3.5 Teeline (WL2)

A small treeline (WL2) was recorded adjacent to the BC4 habitat, where four trees of yulan magnolia were present. Three of the four trees were covered by epiphytic common ivy, and the base of the trees were covered by ruderal species typically found at the base of treelines, as well as ornamental planting at the base of one tree. Therefore, the treeline habitat for this Site has been assigned as **less than local importance**.

6.2.2.3.6 Dry meadows and grassy verges (GS2)

The extent of the dry meadows and grassy verges (GS2) habitat is restricted to the southern boundary of the Site of the Proposed Development. These habitats were dominated by floral species such as perennial ryegrass, nettle, dandelion, coltsfoot (*Tussilago farfara*), spear thistle (*Cirsium vulgare*), hybrid dock (*Rumex sp*), and creeping buttercup (*Ranunculus repens*). Scattered populations of cleavers, common ragwort (*Jacobaea vulgaris*), broad-leaved dock (*Rumex obtusifolius*), goat willow (*Salix caprea*), dogwood (*Cornus sanguinea*), and cotoneaster (*Cotoneaster frigidus*) were recorded.

While no rare or protected floral species were observed in this habitat, invasive butterfly bush and cotoneaster were recorded in scattered distribution across the extent of this habitat. Therefore, the dry meadows and grassy verges habitat for this Site has been assigned as **less than local importance**.

6.2.2.3.7 (Mixed) broadleaved woodlands (MWD1)

The (mixed) broadleaved woodlands habitat was recorded along a small stretch of the eastern boundary of the Site, where the woodlands appear to have been planned as roadside trees for the existing carriageway that runs above the eastern section of the Site. This habitat consisted of a mixture of semi-mature and mature trees of common alder (*Alnus glutinosa*), horse chestnut (*Aesculus hippocastanum*), and sour cherry (*Prunus cerasus*). Therefore, the (mixed) broadleaved woodlands habitat for this Site has been identified as of **local importance**.

6.2.2.3.8 Spoil and bare ground (ED2)

The BL3 habitat recorded along the western section of the Site transitions into the spoil and bare ground habitats along the northern section of the Site of the Development. This habitat was identified due to lack of floral biodiversity due to recurring disturbance, in the absence of which can be colonised by the bordering floral species. Therefore, the spoil and bare ground habitat for this Site has been assigned **less than local importance** in terms of ecological importance.

6.2.2.3.9 Recolonising bare ground (ED3)

The ED3 habitat has been recorded along the northern and eastern section of the Site of the Proposed Development, where floral species such as perennial ryegrass, spear thistle, dandelion, winter heliotrope, broad leaved dock, cleavers and young bramble were observed. Invasive butterfly bush was also recorded in this habitat along its northern extent.

A small section at the northern extent of this habitat along the eastern section of the Site had standing water in it. This small area of the habitat was distinct from other areas of the habitat due to the present of common cattail (*Typha latifolia*) in areas of standing water, and hard rush (*Juncus inflexus*) along the perimeter of the standing water. The absence of water courses on Site and the relatively undisturbed nature of the soil indicated that this area of standing water is transient in nature, only showing water during rainfall events.

Some floral species, namely common ragwort, nettle, saplings of orange ball (*Buddleja globosa*), subterranean clover (*Trifolium subterraneum*), horseweed (*Conyza canadensis*), coltsfoot, juvenile goat willow and saplings of alder were recorded only along the eastern section of this habitat. Therefore, the recolonising bare ground habitat for this Site has been assigned as **less than local importance**.



Figure 6.7: Existing habitats recorded at Plot 2 (St. Mochta's LRD) as assessed during the Site survey conducted on 27th March 2025

6.2.2.4 Species and Species Groups

6.2.2.4.1 Flora

6.2.2.4.1.1 Rare and Protected Flora

Species records available from the National Biodiversity Data Centre (NBDC) online database for the 10 km grid square (O03), 2km grid squares (O03T) and the 1km grid squares (O0637) were studied for the presence of rare or protected flora species. The NBDC datasets for the (O0637) 1km grid square yielded no records. This database contained no records of protected flora within the last 20 years, however, several regionally extinct or vulnerable plant species occurred within the 2km grid squares (O03T), and 10km grid square (O03) are shown in Table 6.14 below.

Table 6.14: Records of Rare or Protected Flora For the Surrounding 10km (O03) and 2km (O03T) grid squares
Associated with the Site from the NBDC

Species	NBDC Grid Square	Date of Last Record	Database	Conservation Status
Common Gromwell (Lithospermum officinale)	O03 (10km)	18/07/2020	Vascular plants: Online Atlas of Vascular Plants 2012 Onwards	Threatened Species: Near threatened
Cornflower	O03 (10km)	26/08/2020	Vascular plants: Online Atlas of	Threatened Species: Waiting
(Centaurea cyanus)	O03T (2km)	7.27	Vascular Plants 2012 Onwards	list
Fragrant Agrimony (Agrimonia procera)	O03 (10km)	04/07/2019	Vascular plants: Online Atlas of Vascular Plants 2012 Onwards	Threatened Species: Near threatened
Greater Knapweed (Centaurea scabiosa)	O03 (10km)	26/03/2022	Vascular plants: Online Atlas of Vascular Plants 2012 Onwards	Threatened Species: Near threatened
Green Figwort (Scrophularia umbrosa)	O03 (10km)	10/07/2020	Vascular plants: Online Atlas of Vascular Plants 2012 Onwards	Threatened Species: Endangered
Hairy St John's- wort (<i>Hypericum</i> <i>hirsutum</i>)	O03 (10km)	22/05/2023	Vascular plants: Online Atlas of Vascular Plants 2012 Onwards	Protected Species: Flora Protection Order. Threatened Species: Endangered
Meadow Crane's- bill (<i>Geranium</i> <i>pratense</i>)	O03 (10km)	08/08/2021	Vascular plants: Online Atlas of Vascular Plants 2012 Onwards	Threatened Species: Vulnerable

Pale Flax (Linum bienne)	003 (10km)	14/07/2021	Vascular plants: Online Atlas of Vascular Plants 2012 Onwards	Threatened Species: Near threatened
Spring Vetch (Vicia lathyroides)	003 (10km)	18/05/2012	Ireland's BioBlitz	Threatened Species: Least concern
Strawberry-tree (Arbutus unedo)	O03 (10km)	26/02/2023	Vascular plants: Online Atlas of Vascular Plants 2012 Onwards	Threatened Species: Near threatened
Yellow Archangel (Lamiastrum galeobdolon)	O03 (10km)	12/05/2018	Vascular plants: Online Atlas of Vascular Plants 2012 Onwards	Threatened Species: Least concern
Yellow Horned- poppy (Glaucium flavum)	O03 (10km)	21/06/2020	Vascular plants: Online Atlas of Vascular Plants 2012 Onwards	Threatened Species: Near threatened

None of the aforementioned protected or rare floral species were recorded on Site during the Site survey conducted on 27th March 2025. Therefore, these species are of **less than local importance** in terms of ecological importance and are not considered further in this report for this Site.

6.2.2.4.1.2 Invasive Species

No invasive floral species were recorded in the (O0637) 1km grid square, and the (O03T) 2km grid squares encompassing the Site of the Proposed Development. However, one medium impact and one high impact invasive species were recorded within the 10km (O03) grid square. The details of these species have been listed in Table 6.15 below.

Table 6.15: Records of Invasive Flora for the Surrounding 10km (O03) Grid square Associated with the Site from the NBDC

Species	NBDC Grid Square	Date of Last Record	Database	Legal Status
Butterfly-bush (Buddleja davidii)	O03	26/02/2023	Vascular plants: Online Atlas of Vascular Plants 2012 Onwards	Medium Impact Invasive Species
Nuttall's Waterweed (<i>Elodea nuttallii</i>)	003	18/07/2020	Vascular plants: Online Atlas of Vascular Plants 2012 Onwards	High Impact Invasive Species Regulation S.I. 477 (Ireland)

Invasive Butterfly-bush was recorded along the eastern extent of the northern hedgerow (WI1), and the= recolonising bare ground (ED3) habitats at the Site of the Proposed Development, as recorded on 27th March 2025 during the Site survey. Therefore, these species are of **less than local importance** in terms of ecological importance and are not considered further in this report for this Site.

6.2.2.4.2 <u>Bats</u>

6.2.2.4.2.1 Desk Study Results

Six bat species were recorded in the 2km (O03T), and 1km (O0537) grid squares encompassing the Site. These species have been listed in Table 6.16 below. Two additional bat species, Natterer's bat (*Myotis nattereri*), and whiskered bat (*Myotis mystacinus*) were recorded in the 10km (O03) grid square encompassing the Site.

Table 6.16: Records of Bat Species for the Surrounding grid squares Associated with the Site from the NBDC

Species	NBDC Grid Square	Date of Last Record	Database	Legal Status
Common Pipistrelle	O0637 (1km)	02/05/2022	National Bat	EU Habitats Directive - Annex
(Pipistrellus	O03T (2km)		Database of Ireland	IV
pipistrellus sensu stricto)	O03 (10km)	15/08/2023	rrelatio	Wildlife Act 1976 (as amended)
	O0637 (1km)	02/05/2022		EU Habitats
Daubenton's Bat (<i>Myotis</i>	O03T (2km)	02,03,2022	National Bat Database of	Directive - Annex IV
daubentonii)	O03 (10km)	03/05/2022	Ireland	Wildlife Act 1976 (as amended)
	O0637 (1km)	15/08/2008		EU Habitats
Lesser Noctule (Nyctalus leisleri)	O03T (2km)	02/05/2022	National Bat Database of	Directive - Annex IV
(Nyctulus leisieri)	O03 (10km)	15/08/2023	Ireland	Wildlife Act 1976 (as amended)
	O0637 (1km)	02/05/2022	National Bat Database of	EU Habitats
Soprano Pipistrelle (<i>Pipistrellus</i>	O03T (2km)			Directive - Annex IV
pygmaeus)	O03 (10km)	15/08/2023	Ireland	Wildlife Act 1976 (as amended)
Brown Long-eared Bat (<i>Plecotus</i>	O03T (2km)	02/05/2022	National Bat Database of	EU Habitats Directive - Annex IV
auritus)	O03 (10km)		Ireland	Wildlife Act 1976 (as amended)
Nathusius's Pipistrelle	O03T (2km)	02/05/2022	National Bat Database of	EU Habitats Directive - Annex IV
(Pipistrellus nathusii)	O03 (10km)	02,03,2022	Ireland	Wildlife Act 1976 (as amended)
Natterer's Bat (Myotis nattereri)	O03 (10km)	30/09/2008	National Bat Database of Ireland	EU Habitats Directive - Annex IV

				Wildlife Act 1976 (as amended)
Whiskered Bat (Myotis mystacinus)	O03 (10km)	03/09/2005	National Bat Database of Ireland	EU Habitats Directive - Annex IV Wildlife Act 1976 (as amended)

The Proposed Development (indicated in the black box in Figure 6.8 below) is located in an area with an overall medium - high (35.44) suitability for bats in general. The suitability index for specific bat species is presented in Table 6.17. The landscape suitability index is high for five species of bats, namely soprano Pipistrelle (*Pipistrellus pygmaeus*), brown long-eared bat (*Plecotus auritus*), common pipistrelle (*Pipistrellus pipistrellus*), Leisler's bat (*Nyctalus leislerii*), and natterer's bat (*Myotis nattereri*). The landscape suitability index is medium – high for two species of bat, namely whiskered bat (*Myotis mystacinus*), and Daubenton's bat (*Myotis daubentonii*).

Table 6.17: Landscape Suitability Index for Individual Bat Species within the 2km grid square (NBDC, 2025).

Those species that have been recorded in the NBDC Database within the O03 10km grid square are highlighted in green

Bat Species	Suitability Index (2km Grid Square)
Soprano pipistrelle (Pipistrellus pygmaeus)	43 (High)
Brown Longed-eared bat (Plecotus auritus)	50 (High)
Common pipistrelle (Pipistrellus pipistrellus)	50 (High)
Lesser horseshoe bat (Rhinolophus hipposideros)	0 (Low)
Leisler's bat (Nyctalus leisleri)	51 (High)
Whiskered bat (Myotis mystacinus)	33 (Medium - High)
Daubenton's bat (Myotis daubentonii)	33 (Medium - High)
Nathusius' pipistrelle (Pipistrellus nathusii)	18 (Low - Medium)
Natterer's bat (Myotis nattereri)	41 (High)



Figure 6.8: Bat landscape suitability model (all bats) surrounding Plot 2 (St. Mochta's LRD) indicated by the black box (NBDC, 2025)

6.2.2.4.2.2 Field Survey Results

6.2.2.4.2.2.1 Bat Roost Assessment and Habitat Suitability

During the Site visit on 27th Mrach 2025, a preliminary bat roost assessment was conducted on all trees within the Site. The preliminary bat roost assessment found that the buildings at the western access point of the Site of the Proposed Development fall under the BCT categories of NONE or PRF-I, whereas the trees along the access gate, trees in the (mixed) broadleaved woodland (MWD1), and hedgerows (WL1) fall under the BCT categories of NONE or PRF-I. Therefore, the Site holds limited potential to support singular opportunistic bat roosts.

The linear hedgerows feature along the western, northern and eastern sections of the Site were assessed as providing 'Moderate' habitat suitability for foraging and commuting bats.

The Site of the Proposed Development is exposed to high light levels given the presence of sport floodlights at the Site. In the vicinity of the Site, the trainline to the north, and residential buildings to the east of the Site expose the Site to very low ambient light level along areas of the Site that are not illuminated by the floodlights. Agricultural fields to the west, and construction works to the south of the Site expose the Site to very low ambient light levels along these areas. However, the majority of the Site is likely to be undisturbed by artificial lighting and is well connected to the surrounding landscape, which consists of linear green corridors along the trainline to the north and existing carriageway along the eastern boundary of the Site. Therefore, the Site is of **less than local importance** for roosting bats but is of **local importance** to commuting and foraging bats.

6.2.2.4.2.2.2 <u>Bat Activity Transect Survey</u>

As per the best standard practice guidelines and the assessment of PBRA assessment conducted for the Site, two seasonal bat activity transect surveys have been recommended, with one survey carried out in May) for Spring), and one survey to be carried out between June and August (for Summer).

6.2.2.4.3 Birds

6.2.2.4.3.1 Desk Study Results

A total of 104 bird species have been recorded within the (O03) 10km grid square, (O03T) 2km grid square, and (O0637) 1km grid squares. Of these, 17 are red listed bird species, 32 are amber listed bird species, and the remaining are green listed bird species (and some bird species with no classification) as identified on the Birds of Conservational Concern in Ireland (BoCCI) (Gilbert er al. 2021). Details of amber and red listed species are detailed in **Error! Reference source not found.** in Appendix 6.1.

6.2.2.4.3.2 Field Survey Results

6.2.2.4.3.2.1 Bird Scoping Survey

A total of seven bird species were observed at the Site during the walkover survey on 27th March 2025, where one of the species recorded was amber listed species as per the Birds of Conservation Concern in Ireland 2020-2026 (Gilbert et al., 2021), namely European Herring Gull (*Larus argentatus*), All of the remaining bird species recorded are green listed species and have been listed in Table 6.18 below. Therefore, the Site is of **local importance** to bird species.

Table 6.18: Bird Species recorded during the walkover survey on 27th March 2025

Species	BoCCI Status
Robin (<i>Erithacus rubecula</i>)	Green
Magpie (<i>Pica pica</i>)	Green
Hooded Crow (Corvus corone)	Green
Wood pigeon (Columba palumbus)	Green
Great Black-backed Gull (Larus marinus)	Green
Great Tit (<i>Parus major</i>)	Green
European Herring Gull (Larus argentatus)	Amber

In addition to the list of bird species observed at the Site, no disused or new nests were found across the Site. However, given the diverse habitats recorded on Site, there is potential for breeding birds to nest at the Site, the scope of which will be assessed in the breeding bird survey.

6.2.2.4.3.2.2 <u>Breeding Bird Surveys</u>

As per the best standard practice guidelines and habitats assessed on the Site, three monthly breeding bird surveys has been recommended to be carried out within the breeding bird season, where the first survey can be carried out in May, followed by surveys in June and early July.

6.2.2.4.4 Mammals (excl. bats)

6.2.2.4.4.1 Desk Study Results

A total of 19 mammals were recorded within the 10km (O03), 2km (O03T), and 1km (O0637) grid squares. Off these, eleven species are native terrestrial mammals, with seven of these species afforded legal protection under the Wildlife (Amendment) Act, 2000, namely badger (*Meles meles*), otter (*Lutra lutra*), pine marten (*Martes martes*), red deer (*Cervus elaphus*), hedgehog (*Erinaceus europaeus*), red squirrel (*Sciurus vulgaris*), and Eurasian pygmy shrew (*Sorex minutus*)

The remaining eight species are considered invasive and/or non-native, namely brown rat (*Rattus norvegicus*), rabbit (*Oryctolagus cuniculus*), brown rat (*Rattus norvegicus*), American mink (*Mustela vison*), eastern grey squirrel (*Sciurus carolinensis*), fallow deer (*Dama dama*), house mouse (*Mus musculus*), Siberian chipmunk (*Tamias sibiricus*), and sika deer (*Cervus nippon*). These species have been recorded across the 10km (O03) grid square encompassing the Site of the Proposed Development.

Table 6.19: Records of mammal species (excl. bats) for the surrounding grid squares associated with the Site from the NBDC

Species	Grid Square	Date of Last Record	Database	Designation
		Native Species		

				\A7:1-11:£
Eurasian Badger (Meles meles)	O03 (10km)	08/04/2023	Mammals of Ireland 2016-2025	Wildlife (Amendment) Act 2000 Berne Convention Appendix III
Eurasian Pygmy Shrew (<i>Sorex</i> minutus)	O03 (10km)	03/10/2015	Atlas of Mammals in Ireland 2010- 2015	Wildlife (Amendment) Act 2000
Eurasian Red Squirrel (<i>Sciurus</i> <i>vulgaris</i>)	O03 (10km)	24/01/2015	Atlas of Mammals in Ireland 2010- 2015	Wildlife (Amendment) Act 2000
European Otter	O03 (10km)	06/12/2018	Mammals of Ireland 2016-2025	Wildlife
(Lutra lutra)	O03T (2km)	20/08/2014	Atlas of Mammals in Ireland 2010- 2015	(Amendment) Act 2000
Irish Hare (Lepus timidus subsp. hibernicus)	O03 (10km)	23/02/2020	Mammals of Ireland 2016-2025	N/A
Irish Stoat (Mustela erminea subsp. hibernica)	003 (10km)	14/04/2024	Irish Stoats of Ireland	N/A
Pine Marten	O03 (10km)	21/05/2021	Mammals of	Wildlife
(Martes martes)	O03T (2km)	17/08/2019	Ireland 2016-2025	(Amendment) Act 2000
Red Deer (<i>Cervus</i> <i>elaphus</i>)	O03 (10km)	31/12/2008	Deer of Ireland Database	Wildlife (Amendment) Act 2000
Red Fox (<i>Vulpes</i>	O03 (10km)	21/01/2023	Mammals of Ireland 2016-2025	
vulpes)	O03T (2km)	28/07/2012	Atlas of Mammals in Ireland 2010- 2015	N/A
West European	O03 (10km)	07/12/2023		Wildlife
Hedgehog (<i>Erinaceus</i>	O03T (2km)	12/05/2021	Hedgehogs of Ireland	(Amendment) Act
europaeus)	O0637 (1km)	05/05/2021		2000
Wood Mouse (Apodemus sylvaticus)	O03 (10km)	20/05/2011	Ireland's BioBlitz	N/A
	Non-	native and Invasive S	pecies	
American Mink (<i>Mustela vison</i>)	O03 (10km)	02/08/2018	Mammals of Ireland 2016-2025	High Impact Invasive Species

				Regulation S.I. 477 (Ireland)
Brown Rat (<i>Rattus</i>	O03 (10km)	20/11/2015	Atlas of Mammals in Ireland 2010- 2015	High Impact Invasive Species
norvegicus)	O03T (2km)	27/09/2014	Atlas of Mammals in Ireland 2010- 2015	Regulation S.I. 477 (Ireland)
Eastern Grey	003 (10km)	17/11/2022	Mammals of Ireland 2016-2025	High Impact Invasive Species
Squirrel (Sciurus carolinensis)	O03T (2km)	23/06/2022	Mammals of Ireland 2016-2025	Regulation S.I. 477 (Ireland)
	O0637 (1km)	25/05/2008	Road Kill Survey	(,
European Rabbit (<i>Oryctolagus</i>	003 (10km)	31/03/2023	Mammals of Ireland 2016-2025	Medium Impact
cuniculus)	O03T (2km)	21/01/2023	Mammals of Ireland 2016-2025	Invasive Species
Fallow Deer (<i>Dama</i>	003 (10km)	19/07/2018	Mammals of	High Impact Invasive Species
dama)		25/6//2525	Ireland 2016-2025	Regulation S.I. 477 (Ireland)
House Mouse (Mus musculus)	O03 (10km)	01/11/2012	Atlas of Mammals in Ireland 2010- 2015	High Impact Invasive Species
Siberian Chipmunk	003 (10km)		National Invasive	High Impact Invasive Species
(Tamias sibiricus)	003 (10km)	15/07/2011	Species Database	Regulation S.I. 477 (Ireland)
Sika Deer (<i>Cervus</i>	003 (10km)	31/12/2008	Deer of Ireland	High Impact Invasive Species
nippon)	COS (IONIII)	31, 12, 2000	Database	Regulation S.I. 477 (Ireland)

6.2.2.4.4.2 Field Survey Results

6.2.2.4.4.2.1 <u>Large Mammals</u>

During the site walkover survey conducted on 27th March 2025, no signs of large mammal species at the Site of the Proposed Development were recorded.

Badger

No direct sightings, badger setts, footprints, latrines, hairs, feeding activity, snuffle holes or badger scat was recorded at the Site of the Proposed Development. This indicated that badgers do not regularly utilise the Site. Furthermore, there are no notable green corridors connecting the Site to the greater area. The only existing corridor is located along the eastern boundary of the Site, where the roadside tree planting associated with the existing carriageway at the eastern boundary of the Site

STEPHEN LITTLE & ASSOCIATES MAY 2025

offered limited connectivity to the south. However, this is considered to be sub-optimal and unlikely to be used by commuting badgers. Given the absence of field signs at the Site of the Proposed Development, it can be concluded that the Site is not used by badgers for foraging, commuting or sett establishment. Therefore, Plot 2 (St. Mochta's LRD) Site is unlikely to be of significant importance to badger population in the greater area and is of **lesser than local importance**.

Otter

No signs of otter activity, such as direct sightings, spraints, holts, couches, footprints or feeding remains were recorded at the Site of the Proposed Development. This indicated that otters are not currently using the Site for activities such as foraging, commuting, or resting. There are no watercourses at the Site of the Proposed Development, and no water courses connecting the Site with the nearby Royal Canal where otters have been listed as QI. Given the lack of connectivity to the Royal Canal stream flowing north of the Site, and absence of watercourses at the Site, it is considered that Plot 2 (St. Mochta's LRD) Site of the Proposed Development is unlikely to be of significant importance to otter populations in the greater area and is of **lesser than local importance**.

Red Deer

During the Site survey, no tracks, droppings, feeding signs, or sightings was recorded at the Site of the Proposed Development. This indicated that red deer do not regularly utilise the Site. Furthermore, there are no significant green corridors connecting the Site to suitable habitats of red deer within the surrounding landscape. Therefore, given the lack of field signs and lack of green corridors, it is considered that the Site of the Proposed Development is unlikely to be of significant importance to red deer populations in the greater area and is of **lesser than local importance**.

Fox

No evidence of fox activity, such as tracks, scat, dens or remains of prey were recorded at the Site of the Proposed Development. Although foxes are common and widespread across Ireland, the absence of field signs suggested that the Site is not of significant importance to local fox populations in the greater area, and the Site itself is of **less than local importance** to this species.

Other mammals

Due to the limited number of large trees with tree hollows or crevices, lack of wooded habitat and lack of ecological corridors for larger mammal species, it is unlikely pine marten, or red squirrel would utilise the Site. Therefore, the Site of the Proposed Development is of **less than local importance** for these species.

6.2.2.4.4.2.2 Smaller Mammals

Suitable habitats for smaller mammal species, such as hedgehogs, hare, wood mouse, and pygmy shrew was recorded along the hedgerows bordering the Site, along with the grassland habitat on Site. The western field parcel, just outside the Site boundary contains a scattered piles of logs and branches, which are suitable hibernacula/refuge for small mammals. However, burrows were not recorded across the Site, indicating the absence of the aforementioned species during the survey.

Although no direct evidence of hedgehogs, hare, wood mouse and pygmy shrew was recorded during the Site walkover, the range of habitats present within the Site, including the hedgerows and grassland habitats are considered to be suitable habitat for these species. Given the timid, nocturnal or cryptic behaviour of some of the aforementioned species, it can be considered that these species may utilise the Site in the future. Therefore, it can be concluded that the Site has the potential to

provide suitable commuting, foraging and resting habitats for smaller mammals, which can be significantly impacted during the Construction and/or Operational Phases of the Proposed Development in the absence of mitigation. For these reasons, the Site of the Proposed Project has been assigned **local level of importance**.

6.2.2.4.5 Amphibians

Both common frog (*Rana temporaria*) and smooth newt have (*Lissotriton vulgaris*) been recorded in the 10km (O03) and 2km (O03T) grid squares encompassing the Site of the Proposed Development.

Table 6.20: Records of amphibians for the surrounding grid squares associated with the Site from NBDC

Species	Grid Square	Date of Last Record	Database	Designation
Common Frog (Rana temporaria)	O03T (2km)	25/02/2023	Amphibians and	Wildlife (Amendment) Act
	003 (10km)	25/02/2023	reptiles of Ireland	2000
Smooth Newt (Lissotriton vulgaris)	003 (10km)	05/04/2023	Amphibians and reptiles of Ireland	Wildlife (Amendment) Act 2000

During the walkover survey on 27th March 2025, habitats on Site were checked for signs of amphibians. No ponds were recorded at the Site, however, a section of the ED3 habitat at the eastern section of the Site consisted of a small area of standing water. No frogs, newts of spawns of these species were recorded in this area during the walkover survey, and the standing water appeared to be transient in nature, only stagnating with water during rainfall events. For these reasons, the Site of the Proposed Development has been assigned **less than local level of importance**.

6.2.2.4.6 Reptiles

No records of common lizard (*Zootoca vivipara*) exist for the relevant 10km (O03), 2km (O03T), and 1km (O0637) grid squares encompassing the Site of the Proposed Development. However, there are some suitable habitats for this species within the Site of the Proposed Development along the hedgerow habitats, as well as waste material (e.g.; concrete blocks) that were located in the ED3 habitat bordering the MWD1 habitat at the eastern section of the Site. As no targeted surveys for common lizard were carried out, it is assumed under the precautionary principle that a locally important population of this species may be present at the Site. Therefore, the Site of the Proposed Development has been identified as **local importance** for common lizards.

Within the 10km (003), 2km (003T), and 1km (00637) grid squares, two invasive reptile species have been listed, namely red-eared terrapin (*Trachemys scripta*), and yellow-bellied slider (*Trachemys scripta scripta*). Whiles there are suitable habitats for these species on Site of the Proposed Development, these species were not recorded during the walkover survey.

6.2.2.4.7 Fish and other Aquatic Species

While protected species such as European eel (*Anguilla anguilla*), and grey seals (*Halichoerus grypus*) have been recorded within the 10km (O03) grid square encompassing the Site of the Proposed Development, there are no waterbodies within the Site of the Proposed Development that could support notable fish or aquatic species.

The Site drainage network during the Operational Phase of the Development does not connect to the Royal Canal stream that flows north of the Site. Therefore, fish and other aquatic species are not a consideration during this phase of the Proposed Development, and the Site is identified as **less than local importance** for fish and other aquatic species.

6.2.2.4.8 Marsh Fritillary

The marsh fritillary (*Euphydryas aurinia*) butterfly is the only insect in Ireland that is listed on Annex II of the Habitats Directive, which makes it the only insect protected by law in Ireland. There are no records of marsh fritillary from the last five years within the 10km (O030) grid square which encompass the Proposed Development. No individuals of this species or it's associated food plant; devil's bit scabious (*Succisa pratensis*), were recorded during the walkover survey on 27th March 2025. It should be noted that devil's bit scabious is an autumn flowering plant and as such may have been missed during the surveys. Additionally, the recommended survey period for marsh fritillary is in September and October when the caterpillars can be found within silken webs on the leaves of the foodplant. The majority of the Site is amenity grassland which is not considered likely to support devil's bit scabious or the marsh fritillary. Therefore, the Site of the Proposed Development is identified as **less than local importance** for marsh fritillary.

6.2.2.4.9 Other Invertebrates

6.2.2.4.9.1 Desk Study Results

Eleven of the invertebrate species were recorded within the 10km (O03), 2km (O03T), and 1km (O0637) encompassing the Site of the Proposed Development. These species are not protected, however are listed as 'Endangered', 'Near Threatened', 'Vulnerable' or 'Data deficient' Conservation status in Ireland.

Table 6.21: Records of rare and invasive invertebrates for the surrounding grid squares associated with the Site from the NBDC

Species	Grid Square	Date of Last Record	Database	Conservation Status		
	Rare Species					
Andrena (Andrena) fucata	O03 (10km)	31/05/2008	Bees of Ireland	Threatened Species: Near threatened		
Andrena (Leucandrena) barbilabris	O03 (10km)	26/04/2022	Bees of Ireland	Threatened Species: Near threatened		
Andrena (Melandrena) nigroaenea	O03 (10km)	02/04/2021	Bees of Ireland	Threatened Species: Vulnerable		
Andrena (Taeniandrena) wilkella	O03 (10km)	31/05/2008	Bees of Ireland	Threatened Species: Data deficient		
Gipsy Cuckoo Bee (Bombus (Psithyrus) bohemicus)	O03 (10km)	29/05/2023	Bees of Ireland	Threatened Species: Near threatened		
Gooden's Nomad Bee (<i>Nomada</i> goodeniana)	O03 (10km) O03T (2km) O0637 (1km)	08/05/2023	Bees of Ireland	Threatened Species: Endangered		
	/					

Halictus (Seladonia) tumulorum	O03 (10km)	30/07/2008	Bees of Ireland	Threatened Species: Near threatened
Large Red Tailed Bumble Bee	O03 (10km)	16/05/2024		Threatened
(Bombus	O03T (2km)	17/04/2023	Bees of Ireland	Species: Near
(Melanobombus) lapidarius)	O0637 (1km)	27/07/2012		threatened
Megachile (Delomegachile) willughbiella	O03 (10km)	17/07/2021	Bees of Ireland	Threatened Species: Near threatened
Megachile (Megachile) centuncularis	O03 (10km)	22/06/2021	Bees of Ireland	Threatened Species: Near threatened
Moss Carder-bee (Bombus (Thoracombus) muscorum))	O03 (10km)	06/05/2021	Bees of Ireland	Threatened Species: Near threatened
Invasive Species				
Harlequin Ladybird	00637 (1km)	02/09/2024	Ladybirds of	High Impact Invasive Species
(Harmonia axyridis)	O03T (2km)		Ireland	Regulation S.I. 477
, ,	O03N (2km)	15/08/2024		(Ireland)

6.2.2.4.9.2 Field Survey Results

During the walkover survey conducted on 27th March 2025, none of the aforementioned rare invertebrate species were recorded. Therefore, the Site of the Proposed Development is identified as **less than local importance** to invertebrate species.

6.2.2.4.10 Protected and/or Notable Species Unlikely to Occur at the Site

Other notable and/or rare species and species listed on Annex IV of the Habitats Directive that were considered but that are unlikely to occur at the Site have been included in Table 6.22 below. The Site of the Proposed Development for these species has been identifies as **less than local importance** for these species.

Table 6.22: Protected and/or notable species unlikely to occur at the Site and the reason for exclusion from assessment

Species	Reason for exclusion from assessment		
Flora			
Marsh Saxifrage (Saxifraga hirculus)	Known populations only in Co. Mayo.		
	Nearest known populations in Co. Wicklow, not		
Killarney Fern (Vandenboschia speciosa)	recorded at the Site, no suitably sheltered and moist		
	habitats available.		
	A clear water, lowland lake species. No		
Slender Naiad (<i>Najas flexilis</i>)	suitable habitat available at the Site.		

Fauna			
	Not present in the Liffey, adjacent ditches and		
White-clawed Crayfish (Austropotamobius pallipes)	streams not considered suitable for this species due		
	to low quality.		
	Nearest known records from the Barrow catchment		
Freshwater Pearl Mussel (Margaritifera	to the west of the Site, no hydrological connection		
margaritifera)	to this catchment. Liffey is not listed as a M.		
	margaritifera sensitive area.		
Natterjack Toad (<i>Epidalea calamita</i>)	Distribution restricted to few coastal sites.		
Kerry Slug (Geomalacus maculosus)	Distribution restricted to south and west of Ireland		

6.2.3 Cumulative

The application sites for Luttrellstown Gate Phase 2 (Plot 1) and St Mochta's LRD (Large Scale Residential Development) (Plot 2) form part of a larger landholding in the townlands of Kellystown, Porterstown and Diswellstown, Clonsilla, Dublin 15, which has been subject to a number of recent planning permissions, summarised below.

The consented Kellystown SHD scheme ABP-312318-21 was granted (with 27no. conditions) on 2 March 2023, under section 9(4) of the Planning and Development (Housing) and Residential Tenancies Act 2016 for a Strategic Housing Development. The consented scheme includes 346no. dwellings (123no. houses and 3no. apartment buildings accommodating 223no. apartment units)1 , 1no. childcare facility (c. 528 sq m) and 1no. retail unit (c. 236 sq m), in buildings ranging from 2 to 8-storeys, and associated site works and 2.1ha public park amenity. The overall gross site area of the entire consented scheme amounts to c. 9.73 ha, at land zoned 'RS' residential, in Eastern Development Area 1 and land zoned 'OS' open space to the south of permitted Kellystown Link Road. The site is otherwise generally bounded by the existing Kellystown Link Road and schools to the south; the Old Porterstown Road and existing St Mochta's FC grounds to the east; Dr Troy Bridge/L3036 Porterstown Link Road also to the east; the Dublin Maynooth rail line and Grand Canal to the north and undeveloped (Luttrellstown Gate) lands to the west.

Amendments to the consented SHD scheme ABP-312318-21 was granted on 21 August 2024 under Reg. Ref. LRD0034-S3 for development comprising of the reconfiguration of Block A, located in the eastern corner of the site, to accommodate 193no. dwellings in total (an increase of 28no. dwellings) in buildings ranging between 2 and 8 storeys in height, with the following residential unit mix: 82no. 1- bed apartment units, 108no. 2-bed apartment units, and 3no. 2-bed duplex units. Associated reconfiguration of internal floor plans to accommodate an increase from 31no. to 34no. apartment units per floor. Reduced floor area of the internal residential amenity area (from c.405.7 sq m to c.120.9 sqm). Reduced floor area of the retail unit (from c.236 sq m to c.200.6 sq m). And all associated and ancillary site development, infrastructural, hard and soft landscaping and boundary treatment works.

A live planning application, currently at Further Information Stage under FW25A/0033E seeks the relocation of St. Mochta's Football Club grounds, to 'OS' zoned lands to the south of Kellystown Link Road and north of the Cemetery lands and Luttrellstown Road, within the new emergent residential neighbourhood of Kellystown, Dublin 15. This is in accordance with Key Objective DA 1.1 for the Eastern Development Area of the Kellystown Local Area Plan.

In November 2020, Fingal County Council published proposals for the development of a link road through the Kellystown lands for public consultation, under the Part 8 development process. Note that the consented Kellystown SHD scheme ABP-312318-21 includes the extension of the 'Kellystown Link Road' west from its existing section serving the school campus and cemetery lands. A single new vehicular access point to residential development in the Kellystown Eastern Development Area extends north from the 'Kellystown Link Road', under SHD ABP-312318-21. Upgrade works to the existing segment of the 'Kellystown Link Road' and its junctions with Porterstown Road and Diswellstown Road/Overbridge are also included in the Kellystown SHD permission.

Potential for in-combination Effects:

The aforementioned planning application shares a direct hydrological and hydrogeological pathway with the Proposed Development via the Royal Canal Stream.

This planning application and its subsequent supporting applications were supported by an AA Screening report prepared by Enviroguide, a DNV Company, that concluded that this planning application either alone or in combination with other planning applications in the vicinity does not have the capacity to cause significant impacts on European sites or other Designated sites via the Royal Canal. Therefore, the combination of surface water inputs to the Royal Canal stream from this development and the Proposed Development is not envisaged to cause significant impacts on the downstream European sites and that an NIS will not be required.

In the wider surrounding area, the following developments are subject of live planning permissions:

- ABP Reg. Ref. 320886-24 (FCC Reg. Ref. LRD0021/S3E) (north of the Dublin-Maynooth Railway Line) issued with a Grant of Permission on 21 January 2025 for the construction of 170 residential units, a café, and a childcare facility, and all associated development works including the demolition of structures, site clearance, and ground levelling.
- ABP Reg. Ref. 315707-23 (FCC Reg. Ref. FW22A/0152) (north of the Dublin-Maynooth Railway Line) issued with a Grant of Permission on 19 December 2023 comprises the construction of a mixed use retail and residential development comprising 1no. food store (2,500sqm GFA), 3 no. retail units (611.8sqm GFA) and 67 no. residential units.2

Potential for in-combination Effects:

The aforementioned planning applications shares a direct hydrological and hydrogeological pathway with the Proposed Development via the Royal Canal Stream.

These planning applications were supported by AA Screening reports that concluded that these planning applications either alone or in combination with other planning applications in the vicinity do not have the capacity to cause significant impacts on European sites or other Designated Sites via the Royal Canal. Therefore, the combination of surface water inputs to the Royal Canal stream from these developments and the Proposed Development is not envisaged to cause significant impacts on the downstream European sutes and that an NIS will not be required for either of the applications.

6.3 Characteristics of the Proposed Development

6.3.1 Proposed Development – Plot 1 (Luttrellstown Gate Phase 2)

6.3.1.1 Site Location

The application site is currently a greenfield site. It is located in the Kellystown Local Area Plan (LAP), north of the new Kellystown Link Road under construction, west of the Porterstown Road and north of Luttrellstown Road. Site location is shown in Figure 6.9.



Figure 6.9: Proposed Site Layout and Location of Plot 1 (Luttrellstown Gate Phase 2) and Plot 2 (St. Mochta's LRD) of the Proposed Development (O'Mahony Pike, 2024)

6.3.1.2 Proposed Development Description

Castlethorn Developments Luttrellstown Limited intends to apply for Permission for a development at a site (c. 3.72ha) at lands in the Townland of Kellystown.

The proposed development comprises 99no. residential units in a mix of houses and duplex units consisting of 71no. 2 storey houses (66no. 3-bedroom and 5no. 4-bedroom), 16no. 3 storey houses (16no. 4-bedroom), 4no. 1-bedroom duplex units and 8no. 2-bedroom duplex units and all associated and ancillary site development and infrastructural works, hard and soft landscaping and boundary treatment works, including public open space; public lighting; surface car parking spaces; bicycle parking spaces/stores for mid-terrace units; bin stores. The proposed development includes a minor amendment to development permitted under Reg. Ref. ABP-312318-21, as amended by Reg. Ref. LRD0034-S3, with minor adjustment proposed to the permitted surface water attenuation pond. Vehicular access to the proposed development is provided by the road network permitted under Reg. Ref. ABP-312318-21, as amended by Reg. Ref. LRD0034-S3.

6.3.1.3 Drainage and Water Supply

The following surface water and foul drainage information is extracted from the Engineering Assessment Report by Waterman Moylan (Waterman, 2025a).

As the Site is currently greenfield, it is proposed that new separate surface and foul drainage systems are to be installed at the Site to serve the Proposed Development.

6.3.1.3.1 Surface water Drainage

As per the Engineering Assessment Report (Waterman, 2025a), a new surface water drainage has been proposed for the Site, such that surface water at the Site will drain via a series of drains and sewers, ultimately discharging through a separate network on the adjacent Strategic Housing Development under construction under ABP-312318-21.

The rate of discharge of surface water will be restricted by a hyrdrobrake or similarly approved flow control device to ensure that the discharge rate is equivalent to the greenfield runoff rate. In the event that the surface water run off rate exceed the greenfield runoff rate, the excess water will be attenuated. As per the design, it is proposed that surface water for this Site will drain through a separate 520Ø millimetre (mm) pipe on the phase 1 lands, where the water will be directed to the phase 1 attenuation pond which will be increased in size to accommodate drainage from the Site of the Proposed Development. This increased size of the attenuation pond has been designed to accommodate runoff volumes up to 1-in-100-year storm, accounting for a 20% increase due to climate change.

For the purpose of attenuation, the Site of the Proposed Development has been divided into 4 sub-catchments, such as:

- Catchment 1: This includes Blocks H, J and houses in the northeast part of the Site.
- Catchment 2: This includes houses in the southeast part of the Site.
- Catchment 3: This includes houses in the southwest part of the Site.
- Catchment 4: This includes houses in the west and northwest parts of the Site.

In addition, surface water sewers will be laid strictly in accordance with Fingal County Council requirements for taking in charge and will generally consist of PVC (to IS 123) or concrete socket and spigot pipes (to IS 6). All private outfall manholes will be built in accordance with the Greater Dublin Regional Code of Practice for Drainage Works, and no private drainage will be located within public areas.

6.3.1.3.1.1 Sustainable Drainage System

As part of the Proposed Development, a number of different Sustainable Drainage Systems (SuDS) measures are proposed to minimise the impact on water quality and water quantity of the runoff and maximise the amenity and biodiversity opportunities within the site.

The usage of various SuDS techniques has allowed for the incorporation of a Storm Water Management Plan, which will enable treatment and minimization of surface water runoffs from the Site. The methodology involved in developing a Storm Water Management Plan for the subject site is based on recommendations set out in the Greater Dublin Strategic Drainage Study (GDSDS) and in the SuDS Manual (Ciria C753). Based on three key elements – Water Quantity, Water Quality and Amenity – the targets of the SuDS train concept have been implemented in the design, providing SuDS devices for Source Control, Site Control and Regional Control.

It is proposed to provide the following SuDS measures:

- Green roofs on the roofs of the buildings, covering approximately 200.6m2 or a minimum of 60% of roof area.
- Permeable paving in all private driveways and parking courts throughout the Proposed Development.
 Downpipes from the front of the houses and duplex-type units will drain into filter drains beneath the permeable paving to facilitate maximum infiltration of surface water from driveways and roof areas.
- Filter Drains consisting of perforated pipes surrounded by filter stone will be installed around the perimeter of the buildings and beneath the permeable paving parking space. These perforated pipes will connect to the proposed surface water sewer network.
- Tree Pits and planting areas will be introduced at the car park on the Site of the Proposed
 Development. Surface water runoff from the roads will drain to the tree pits, where a high level gully
 will allow any excess water to discharge below-ground surface water network in the event that the
 tree pits and/or landscaped areas become inundated.

- Attenuation and flow control: For this Site, the attenuation storage required for the 1-in-100-year
 storm will be provided by enlarging the detention basin constructed as part of the permitted phase 1
 works, where flows will be controlled by a hydrobrake or similarly approved flow control device. While
 this SuDs is limited to the greenfield equivalent runoff rates, any excess flows will be attenuated in
 the dry detention basin before outfalling by gravity.
- Petrol Interceptor: A Class 1 petrol interceptor will be installed before the surface water outfall, and will function to remove light pollutants, and some hydrocarbons, such as petroleum and diesel (hydrocarbons with less density than water), and in turn protecting the natural watercourse from any contaminated waters.

6.3.1.3.2 Foul drainage

The adjacent Kellystown Strategic Housing Development, under construction by the Applicant under ABP-312318-21 has provided a new foul drain under the new Kellystown Link Road with a spur left to serve the Site of the Proposed Development. This foul sewer drains to a new pumping station, also permitted and under construction under ABP-312318-21. This pumping station has been designed to cater to lands within the entire Local Area Plan(LAP), including the Site, and is due to become operational in 2025.

As per the Engineering Assessment Report (Waterman, 2025a), all wastewater/ foul water from the Site of the Proposed Development will drain by gravity, via the foul water drainage network, into the existing spur located west of the Site, from the Porterstown Road sewer, which has been constructed to facilitate the Site. All foul water from the Site will drain through a separate 300Ø mm pipe on the phase 1 lands, which will consequently drain to the 450Ø mm pipe immediately north of the foul water pumping station (which is currently under construction). This foul water pumping station has been designed to cater to the Site and includes storage of foul water for 24-hours.

The foul water sewers at the Site will be constructed strictly in accordance with Uisce Éireann requirements, and no private drainage will be located within public areas.

6.3.1.4 Landscape Plan

The proposed landscaping of the Site has been prepared by Doyle & O'Troithigh Landscape Architecture Ltd. (Doyle, 2025a). The landscaping at the Site includes additional planting and augmentation of the boundary hedgerows, particularly in the northern boundary.

There are two pocket parks proposed throughout the Site, where a small pocket park will be installed at the southwest corner of the Site, and a larger pocket park will be installed in the central areas of the Site (see Figure 6.10). While discontinuous green spaces have been proposed along the perimeter of each block and along roads within the Site, large continuous green spaces are proposed along the eastern and southern boundaries where mixed woodland, street trees, shrub, wildflower meadows, and hedgerows have been proposed to be planted to act as a buffer.

The landscaping plans have also incorporated the SuDS designs and biodiversity enhancement features such as swales, a raingarden in identified areas of the Proposed Development.



Figure 6.10: Proposed Landscape plan for Plot 1 (Luttrellstown Gate Phase 2) (Doyle, 2025a)

6.3.1.5 Lighting Plan

The lighting plan for the Site of the Proposed Development has been prepared by Sabre Electrical Services Ltd. The following information has been extracted from Sabre Electrical Services Ltd. Outdoor Lighting Report (Sabre 2025):

The lighting design will provide adequate illuminance for vehicular and pedestrian access using low energy LED lighting to minimise both energy consumption and lighting pollution to surrounding area.

6.3.1.6 Description of the Construction Phase

A draft Construction Environmental Management Plan (CEMP) has been prepared by Enviroguide, a DNV Company (Enviroguide, 2025) with details of the Construction Phase for the Site.

It is anticipated that the construction of the Proposed Development will commence in Q2 of 2026 and will be completed by the end of 2027. The programme duration and proposed sequence of construction will be finalized by the Main Contractor (once appointed) in advance of construction works commencing onsite and will be agreed with the Client. The project programme, which may be amended over the course of the project, will be included in the live CEMP.

Except where otherwise agreed with Fingal County Council, working hours will be 08:00-18:00 from Monday to Friday (excluding bank holidays), and 08:00-13:00 on Saturday. No works are envisaged to be carried out on Sundays or Bank Holidays. However, should there be a need to work on Sundays, Bank Holidays or outside the specified normal working hours, a written submission, with compelling reasons for the proposed deviation, seeking authorisation will be made by the Main Contractor (once appointed) to Fingal County Council.

In advance of the commencement for construction the following will be implemented:

- Pre-construction surveys.
- The contractor will secure the Site.

Establishment of accommodation and welfare facilities for workers.

During construction the following will be implemented:

- Dust, noise and vibrations control measures will be implemented to protect the surrounding residential areas and environment.
- Acceptable excavation material will be reused, while unacceptable material will be transported off site to a licensed waste disposal facility.
- Excavation and construction works will be carefully managed to ensure no contamination of watercourses as a result of the construction work.
- Adherence to best practice in respect of protection of the watercourses during all stages of construction.
- Suitable surface water management. Any surface water encountered during this phase will be pumped to the foul sewerage network during periods of low flow in agreement with the relevant authorities or pumped to tankers and removed from site. In the event of an unexpected underground stream being encountered, this will be diverted in consultation with relevant agencies before excavation works continue.
- Protection of existing buildings in the vicinity of the Site.
- Focussed and controlled lighting during construction.

6.3.1.7 Description of the Operational Phase

The Operational Phase of the Proposed Development at Plot 1 (Luttrellstown Gate Phase 2) will comprise of the occupancy of the completed residential development.

6.3.2 Proposed Development- Plot 2 (St. Mochta's LRD).

6.3.2.1 Site Location

The application site is currently in use as football pitches for St. Mochta's Football Club, however, an application from the applicant has recently been lodged comprising of the relocation of St. Mochta's Football Club grounds within the new emergent residential neighbourhood of Kellystown, Dublin 15, in accordance with Key Objective DA 1.1 for the Eastern Development Area of the Kellystown Local Area Plan (see Figure 6.9). The application site, measuring approximately 4.38 hectares, is bounded by Diswellstown Road/Dr. Troy Bridge to the east, the Royal Canal and Dublin-Maynooth Railway Line to the north, and proposed development (Ref. LRD0034-S3) to the south. It also borders residential zoned lands.

6.3.2.2 Proposed Development Description

Castlethorn Developments Luttrellstown Limited intends to apply for Permission for a development at a site (c. 4.38ha) at lands in the Townland of Porterstown.

The proposed development comprises 302no. residential units in a mix of houses, duplex and apartment units consisting of 62no. 2 storey, 3-bedroom houses and 35no. 3 storey, 4-bedroom houses; 205no. Duplex / Apartment Units (98no. 1-bed, 88no. 2-bed and 19no. 3-bed) across 4no. blocks comprising: Block D ranging in height from 5-7 storeys accommodating 57no. apartment units; Block E ranging in height from 5-7 storeys accommodating 77no. apartment units; Block F ranging in height from 4-5 storeys accommodating 39no. apartment and duplex units; Duplex Blocks G1, G2, G3 & G4 3 storeys in height accommodating 32no. apartment units; and all associated and ancillary site development and infrastructural works, hard and soft landscaping and boundary treatment works, including public open space; public lighting; surface car parking spaces; bicycle parking spaces/stores for mid-terrace units; bin stores. Vehicular access to the proposed

development is provided by the road network permitted under Reg. Ref. ABP-312318-21, as amended by Reg. Ref. LRD0034-S3.

The Demolition Phase of the Proposed Development will include the demolition and removal of the existing vacant house and agriculture buildings (including very poor-quality sheds or shipping containers). The total volume of the buildings to be demolished are 863m³.

It is estimated by the Main Contractor that the Construction Phase of the Proposed Development will involve the excavation of 5000m³ of soil for the construction of building foundations, drainage and other infrastructure to depths up to approximately 2m meters below ground level (mbGL) across both plots. It is anticipated that all surplus soil arising from groundworks will require off-site removal for reuse or recovery in accordance with appropriate statutory consents and approvals.

The Construction Phase of the Proposed Development will also require the importation of aggregate fill materials (e.g., granular material beneath road pavement, under floor slabs and for drainage and utility bedding / surrounds etc.).

The Proposed Development Site layout for Plot 2 is presented in Figure 6.11.

6.3.2.3 Drainage and Water Supply

The following surface water and foul drainage information is extracted from the Engineering Assessment Report by Waterman Moylan (Waterman, 2025b).

As the Site is currently greenfield, it is proposed that new separate surface and foul drainage systems are to be installed at the Site to serve the Proposed Development.

6.3.2.3.1 Surface water Drainage

As per the Engineering Assessment Report (Waterman, 2025b), a new surface water drainage has been proposed for the Site, such that surface water at the Site will drain via a series of drains and sewers, ultimately discharging to the spur at the south-east corner of the subject development associated with the adjacent Strategic Housing Development under construction under ABP-312318-21. The surface water will drain into Block A (Reg. Ref. LRD0034/S3) drainage (currently under construction) which in turn drains to Kellystown SHD Phase 1. The drainage through this adjacent space has been constructed by the Applicant under ABP-312318-21, with spurs left to serve the Site of the Proposed Development.

The rate of discharge of surface water will be restricted by a hyrdrobrake or similarly approved flow control device to ensure that the discharge rate is equivalent to the greenfield runoff rate. In the event that the surface water run off rate exceed the greenfield runoff rate, the excess water will be attenuated. The attenuation has been designed to accommodate runoff volumes up to 1-in-100-year storm, accounting for a 20% increase due to climate change.

For the purpose of attenuation, the Site of the Proposed Development has been divided into 2 subcatchments, such as

- Catchment 1: This includes Block D, and houses/duplexes in the northern part of the Site.
- Catchment 2: This includes Block E, F, G1, G2, and G3, and houses/duplexes in the southern part of the Site.

In addition, surface water sewers will be laid strictly in accordance with Fingal County Council requirements for taking in charge and will generally consist of PVC (to IS 123) or concrete socket and spigot pipes (to IS 6). All private outfall manholes will be built in accordance with the Greater Dublin Regional Code of Practice for Drainage Works, and no private drainage will be located within public areas.

6.3.2.3.1.1 Sustainable Drainage System

As part of the Proposed Development, a number of different Sustainable Drainage Systems (SuDS) measures are proposed to minimise the impact on water quality and water quantity of the runoff and maximise the amenity and biodiversity opportunities within the site.

The usage of various SuDS techniques has allowed for the incorporation of a Storm Water Management Plan, which will enable treatment and minimization of surface water runoffs from the Site. The methodology involved in developing a Storm Water Management Plan for the subject site is based on recommendations set out in the Greater Dublin Strategic Drainage Study (GDSDS) and in the SuDS Manual (Ciria C753). Based on three key elements – Water Quantity, Water Quality and Amenity – the targets of the SuDS train concept have been implemented in the design, providing SuDS devices for Source Control, Site Control and Regional Control.

It is proposed to provide the following SuDS measures:

- Green roofs will be installed on the roofs of Blocks D, E, F, G1, G2, and G3, covering approximately 1797m² or a minimum of 60% of roof area.
- Permeable paving in all private driveways and car parking spaces throughout the Proposed Development. Downpipes from the buildings will drain into filter drains beneath the permeable paving to facilitate maximum infiltration of surface water from roof areas.
- Filter Drains consisting of perforated pipes surrounded by filter stone will be installed around the perimeter of the buildings and beneath the permeable paving parking space. These perforated pipes will connect to the proposed surface water sewer network.
- Tree pits and planting areas will be introduced at the car parking areas on the Site of the Proposed
 Development. Surface water runoff from the roads will drain to the tree pits, where a high level gully
 will allow any excess water to discharge below-ground surface water network in the event that the
 tree pits and/or landscaped areas become inundated.
- Petrol Interceptor: A Class 1 petrol interceptor will be installed before the surface water outfall, and will function to remove light pollutants, and some hydrocarbons, such as petroleum and diesel (hydrocarbons with less density than water), and in turn protecting the natural watercourse from any contaminated waters.

6.3.2.3.2 Foul drainage

The adjacent Kellystown Strategic Housing Development, under construction by the Applicant under ABP-312318-21 has provided a new foul drain under the new Kellystown Link Road with a spur left to serve the Site of the Proposed Development. This foul sewer drains to a new pumping station, also permitted and under construction under ABP-312318-21. This pumping station has been designed to cater to lands within the entire Local Area Plan(LAP), including the Site, and is due to become operational in 2025.

As per the Engineering Assessment Report (Waterman, 2025b), all wastewater/ foul water from the Site of the Proposed Development will drain by gravity, via the foul water drainage network, into the existing spur located west of the Site, which has been constructed to facilitate the Site. All foul water from the Site will drain through a separate 300Ø mm upsized pipe on the adjacent phase 1 lands, which will consequently drain to the 450Ø mm pipe immediately north of the foul water pumping station (which is currently under construction). This foul water pumping station has been designed to cater to the Site and includes storage of foul water for 24-hours.

The foul water sewers at the Site will be constructed strictly in accordance with Uisce Éireann requirements, and no private drainage will be located within public areas.

6.3.2.4 Landscape Plan

The proposed landscaping of the Site has been prepared by Doyle & O'Troithigh Landscape Architecture Ltd. (Doyle, 2025b). The landscaping at the Site includes additional planting and augmentation of the boundary hedgerows, particularly the western and northern hedgerows.

The linear park to the Eastern boundary of the site development lands has been designed as the primary area of public open space. The design of this linear park consists of a series of four pocket open space lawn areas, where each of the individual pocket lawns will be surrounded by woodland planting. Two of the four lawn pockets will be sunken to accommodate surface water attenuation.

While discontinuous green spaces have been proposed along the perimeter of each block and along roads within the Site, large continuous green spaces are proposed along the eastern, northern and western boundaries of the Site, mixed woodland, street trees, hedgerows and shrubs have been proposed to be planted to act as a buffer.



Figure 6.11: Proposed Landscape plan for Plot 2 (St. Mochta's LRD) (Doyle - LRD, 2025b)

6.3.2.5 Lighting Plan

The lighting plan for the Site of the Proposed Development has been prepared by Sabre Electrical Services Ltd. The following information has been extracted from Sabre Electrical Services Ltd. Outdoor Lighting Report (Sabre 2025):

The lighting design will provide adequate illuminance for vehicular and pedestrian access, and communal open spaces using low energy LED lighting to minimise both energy consumption and lighting pollution to surrounding area.

6.3.2.6 Description of the Construction Phase

A draft Construction Environmental Management Plan (CEMP) has been prepared by Enviroguide, a DNV Company (Enviroguide, 2025) with details of the Construction Phase for the Site.

It is anticipated that the construction of the Proposed Development will commence in Q3 of 2026 and will be completed by Q2 of 2029. The programme duration and proposed sequence of construction will be finalized by the Main Contractor (once appointed) in advance of construction works commencing onsite and will be agreed with the Client. The project programme, which may be amended over the course of the project, will be included in the live CEMP.

Except where otherwise agreed with Fingal County Council, working hours will be 08:00-18:00 from Monday to Friday (excluding bank holidays), and 08:00-13:00 on Saturday. No works are envisaged to be carried out on Sundays or Bank Holidays. However, should there be a need to work on Sundays, Bank Holidays or outside the specified normal working hours, a written submission, with compelling reasons for the proposed deviation, seeking authorisation will be made by the Main Contractor (once appointed) to Fingal County Council.

In advance of the commencement for construction the following will be implemented:

- Pre-construction surveys.
- The contractor will secure the Site.
- Establishment of accommodation and welfare facilities for workers.
 During construction the following will be implemented:
- Dust, noise and vibrations control measures will be implemented to protect the surrounding residential areas and environment.
- Acceptable excavation material will be reused, while unacceptable material will be transported off site to a licensed waste disposal facility.
- Excavation and construction works will be carefully managed to ensure no contamination of watercourses as a result of the construction work.
- Adherence to best practice in respect of protection of the watercourses during all stages of construction.
- Suitable surface water management. Any surface water encountered during this phase will be pumped to the foul sewerage network during periods of low flow in agreement with the relevant authorities or pumped to tankers and removed from site. In the event of an unexpected underground stream being encountered, this will be diverted in consultation with relevant agencies before excavation works continue.
- Protection of existing buildings in the vicinity of the Site.
- Focussed and controlled lighting during construction.

6.3.2.7 Description of the Operational Phase

The Operational Phase of the Proposed Development at Plot 2 (St. Mochta's LRD) will comprise of the occupancy of the completed residential development.

6.4 Potential Impact of the Proposed Development

6.4.1 Proposed Development - Plot 1 (Luttrellstown Gate Phase 2)

6.4.1.1 Avoidance and Mitigation Embedded in the Project Design

The Proposed Development includes several embedded design features that may act to avoid or mitigate negative impacts that would likely occur in the absence of these features. However, as opposed to typical mitigation measures, the implementation of these features is part of the overall design of the Proposed Development, and as such the impact assessments are performed with consideration of these features as integrated parts of the Proposed Development. All considered embedded design features that may act to mitigate negative impacts on local ecology and environment are listed in Table 6.23 below.

Table 6.23: Embedded design features and their potential to act to avoid or mitigate negative impacts on the local ecology and environment

Embedded Design Features	Avoidance / Mitigation Potential
--------------------------	----------------------------------

SUDS:		
Green roofs		
Permeable paving	The SUDS features included in the Project Design will ensure the surface water discharge from the	
Filter drain	Proposed Development is reduced to greenfield	
Tree pits	runoff rates. These features will be implemented as part of the surface water drainage design.	
Attenuation and flow control		
Petrol interceptor		
Landscape Design:		
Hedgerow, shrub, woodland/street tree, and wildflower grass meadows	This will provide habitat for the biodiversity that currently exists on Site, and act to offset potential habitat loss due to vegetation removal.	
Two pocket parks/ park	o de la companya de	
<u>Lighting Design:</u>	The lighting design will reduce light spill into	
Public lighting will adhere to best practice guidance.	adjacent habitats to maintain dark corridors along the boundaries at the Site and reduce overall	
Light spill controlled through a combination of directional lighting and luminaire optics design.	artificial lighting impacts to any nocturnal wildlife active within or adjacent to the Site during peak	
No floodlighting will be used on the scheme.	active times at night.	

6.4.1.2 Construction Stage Impact Assessment

The impacts of the Construction Phase of the Proposed Development at Plot 1 (Luttrellstown Gate Phase 2) on the identified KERs have been assessed, and Table 6.24 below summaries the evaluation rating assigned to each ecological feature and the rationale behind these evaluations is also provided.

Table 6.24: Evaluation of designated sites, habitats, flora and fauna recorded within the Site for the Construction Phase of Plot 1 (Luttrellstown Gate Phase 2). Those identified as Key Ecological Receptors (KERs) are highlighted in green

Species / Species Group	Evaluation	Rationale	Key Ecological Receptor (KER)
	Designa	ted Sites	
European Sites	International importance (No impact)	No significant S-P-R pathways to European Sites. Mitigations have been included in this EIA report to rule out any potential significant effects on any European sites because of the Proposed Development.	No
Nationally designated sites (pNHAs, NHAs)	National importance (Slight impact)	No significant S-P-R pathways to designated sites. Mitigations have	No
International Sites (Ramsar, UNESCO)	International importance	been included in this EIA report to rule out any potential significant effects on any	No

	(No impact)	designated sites because of the Proposed Development	
	Habitats	and Flora	
Hedgerows (WL1)	Local importance	Comprises native hedgerow species and provides suitable nesting and foraging habitat for a range of species. Sections of the hedgerow along eastern, western and southern extents of this habitat will be retained. However, this habitat may be indirectly affected by the Proposed Development through dust deposition or root damage.	Yes
Improved agricultural grassland (GA1)	Less than local importance	The loss of this low value habitat will not be significant. This habitat type is also abundant in the wider area east of the Proposed Development.	No
Spoil and bare ground (ED2)	Less than local importance	The loss of this low value habitat will not be significant.	No
	Fau	ına	
	Roosting: Less than local importance.	PRF-I potential for roosting bats and moderate suitability for commuting and foraging bats. Details of abundance and species diversity of bats for the site will be confirmed	
Bats	Commuting and Foraging: Local importance	after the required bat surveys to be conducted for the Site are complete. Bat species utilising the Site have the potential to be significantly affected by the Proposed Development in the absence of mitigation.	Yes

Birds	Local Importance	Only green listed bird species were recorded at the Site with suitable breeding habitats for a few notable species. Details of the species diversity of birds for the Site will be confirmed after the required bird surveys to be conducted for the Site are complete. Bird species utilising the Site have the potential to be significantly affected by the Proposed Development in the absence of mitigation.	Yes
Large Mammals	Less than local importance	No resting sites, foraging or commuting habitats for mammals such as badger or otter were identified at the Site. Therefore, it is presumed that the Site is not of importance to these species	No
Small Mammals (excl. bats)	Local Importance	Suitable habitats present for some of the small native mammals, such as hedgehog, hare, pygmy shrew, and wood mouse at the Site, which may be more timid and less likely to be recorded during surveys. Hedgehog specifically hibernate and may be susceptible to injury during vegetation clearance during hibernation in the absence of mitigation.	Yes
Common Lizard	Local Importance	Some suitable habitats in the form of hedgerows and grassland habitats at the Site may provide basking spots, and adjacent scrub that may provide refugia. No desk study records but this species	Yes

		is widespread throughout Ireland and thus presumed present.	
Fish, amphibian and other aquatic species	Less than local importance	Although there is a stagnant water pond at the northwest section of the Site, this is to be retained and do not hold suitability for fishes, amphibians, and other aquatic species as a result of the polluted nature of the pond and lack of flow into or out of the pond.	No

6.4.1.3 Operational Stage

The impacts of the Operational Phase of the Proposed Development at Plot 1 (Luttrellstown Gate Phase 2) on the identified KERs have been assessed, and Table 6.25 below summaries the evaluation rating assigned to each ecological feature and the rationale behind these evaluations is also provided.

Table 6.25: Evaluation of designated sites, habitats, flora and fauna recorded within the Site for the Operational Phase of Plot 1 (Luttrellstown Gate Phase 2). Those identified as Key Ecological Receptors (KERs) are highlighted in green

Species / Species Group	Evaluation	Rationale	Key Ecological Receptor (KER)
	Habitats	and Flora	
Hedgerows (WL1)	Local importance	Sections of the native hedgerows along the eastern, western and southern boundaries of the Site will be retained. While this habitat provides suitable nesting and foraging habitats for a range of bird species, and commuting habitats for bats, the hedgerows along the Site will be enhanced via tree planting as per the landscape design for the Operational Phase of the Proposed Development. Therefore the positive impact will act to offset some of the negative impacts from the loss of this habitat.	Yes
Improved agricultural grassland (GA1)	Less than local importance	The loss of this low value habitat will not be significant. As per the landscape design for the	No

		Site, the planting of woodland, street trees, hedgerows and scrub for the Operational Phase of the Proposed Development will enhance the biodiversity of the Site. The loss of this low value	
Spoil and bare ground (ED2)	Less than local importance	habitat will not be significant. As per the landscape design for the Site, the planting of woodland, street trees, hedgerows and scrub for the Operational Phase of the Proposed Development will enhance the biodiversity of the Site.	No
	Fau	una	1
	Roosting: Less than local importance	Given the current relatively urban context of the Site, an increase in lighting during the Operational Phase of the Proposed Development will have a negative impact on local bat populations through the loss of dark foraging and commuting corridors.	
Bats	Commuting and Foraging: Local Importance	However, the bat friendly lighting measures in line with the Bat Conservation Trust guidelines on artificial lighting and bats has been incorporated into the lighting design plan. Therefore, the positive impact will act to offset some of the negative	Yes
Birds	Local importance	impacts from the loss of habitats for bats. Although negative impacts are envisaged due to the loss of suitable breeding habitats for bird species, the planting of street trees, woodlands, scrub	Yes

and enhancement of hedgerows for the Operational Phase of the Proposed Development will provide a positive impact on bird species.

<u>Likelihood of Collision</u> <u>Impacts</u>

While the physical location of buildings and structures can influence the likelihood of bird collisions, the Site itself is located within a combination of urban and agricultural lands and is not deemed to be located in a sensitive area in terms of bird flight paths i.e., it is not located along the coast, or adjacent to any SPAs designated for wetland bird populations.

Building Height

The Proposed
Development entails the construction of low-level residential buildings and as such, the risk of migrating birds colliding with the structure due to its height is deemed to be negligible

Building Appearance

The overall façades of the proposed buildings are well broken up, with a varied material composition interspersing any reflective areas. These architectural design features provide important visible cues as to the presence and extent of the proposed structures to any commuting/foraging bird species should they be in the vicinity of the Site.

STEPHEN LITTLE & ASSOCIATES MAY 2025

Large Mammals	Less than local importance	No resting sites, foraging or commuting habitats for mammals such as badger or otter were identified at the Site. Therefore, it is deemed that the Site will have negligible impact on the habitats of large mammals during the Operational Phase of the Proposed Development.	No
Small Mammals (excl. bats)	Local Importance	Noise, increase in light, and potential physical disturbance due to increased human presence associated with the Operational Phase has the potential to cause a negative, permanent, moderate impact to small mammals in the absence of suitable mitigation. The Proposed Development will also result in a loss of foraging and commuting habitat for small mammals, however due to the extent of the surrounding suitable habitat in the vicinity of the Site, and considering the new green spaces proposed for installation at the Site, these factors have the potential to cause a negative, permanent, slight impact to small mammals.	Yes
Common Lizard	Local importance	No significant impacts on lizards are anticipated during the Operational Phase. The proposed planting at the Site has the potential to provide a positive, permanent, slight impact. Further consideration of this will be provided once the	Yes

		final planting plans are prepared.	
Fish, amphibian and other aquatic species	Less than local importance	Impacts on fishes, amphibians and other aquatic species is not envisaged due to the proposed SuDS measures that have been incorporated into the landscape design for the Operation Phase of the Proposed Development	No

6.4.1.4 Do-Nothing Impact

Under the do-nothing scenario, most of the habitats at the Site of the Proposed Development would continue to undergo succession. The construction works for the Strategic Housing Development (ABP-312318-21) adjacent to the Site has already commenced and will significantly impact the hedgerows along the eastern and southern boundaries of the Site. The construction of the aforementioned development will result in a change in habitat connectivity to the western field parcels adjacent to the Site via its southern boundary.

The other remaining hedgerows would continue to serve as biodiversity corridors, providing habitat connectivity, along with nesting/roosting and foraging habitat for birds and mammals. The grassland would also continue to provide foraging and commuting habitat for local wildlife and pollinators, with potential for scrub species along the hedgerow to further encroach into the grassland area.

6.4.2 Proposed Development- Plot 2 (St. Mochta's LRD).

6.4.2.1 Avoidance and Mitigation Embedded in the Project Design

The Proposed Development includes several embedded design features that may act to avoid or mitigate negative impacts that would likely occur in the absence of these features. However, as opposed to typical mitigation measures, the implementation of these features is part of the overall design of the Proposed Development, and as such the impact assessments are performed with consideration of these features as integrated parts of the Proposed Development. All considered embedded design features that may act to mitigate negative impacts on local ecology and environment are listed in Table 6.26 below.

Table 6.26: Embedded design features and their potential to act to avoid or mitigate negative impacts on the local ecology and environment

Embedded Design Features	Avoidance / Mitigation Potential	
SUDS:		
Green roofs	The SUDS features included in the Project Design will ensure the surface water discharge from the Proposed Development is reduced to greenfield runoff rates. These features will be implemented as part of the surface water drainage design.	
Permeable paving		
Filter drain		
Tree pits		
Attenuation		

Petrol interceptor		
<u>Landscape Design:</u>		
Hedgerow, shrub, woodland/street tree, and wildflower grass meadows	This will provide habitat for the biodiversity that currently exists on Site, and act to offset potential	
Park with four lawn pockets and surrounding woodland plantation	habitat loss due to vegetation removal.	
<u>Lighting Design:</u>	The lighting design will reduce light spill into	
Public lighting will adhere to best practice guidance.	adjacent habitats to maintain dark corridors along the boundaries at the Site and reduce overall	
Light spill controlled through a combination of directional lighting and luminaire optics design.	artificial lighting impacts to any nocturnal wildlife active within or adjacent to the Site during peak	
No floodlighting will be used on the scheme.	active times at night.	

6.4.2.2 Construction Stage Impact Assessment

The impacts of the Construction Phase of the Proposed Development at Plot 2 (St. Mochta's LRD) on the identified KERs have been assessed, and Table 6.27 below summaries the evaluation rating assigned to each ecological feature and the rationale behind these evaluations is also provided.

Table 6.27: Evaluation of designated sites, habitats, flora and fauna recorded within the Site for the Construction Phase of Plot 2 (St. Mochta's LRD). Those identified as Key Ecological Receptors (KERs) are highlighted in green

Species / Species Group	Evaluation	Rationale	Key Ecological Receptor (KER)		
Designated Sites					
European Sites	International Importance (No impact)	No significant S-P-R pathways to European Sites. Mitigations have been included in this EIA report to rule out any potential significant effects on any European sites because of the Proposed Development.	No		
Nationally designated sites (pNHAs, NHAs)	National Importance (Slight impact)	No significant S-P-R pathways to designated sites. Mitigations have	No		
International Sites (Ramsar, UNESCO)	International Importance (No impact)	been included in this EIA report to rule out any potential significant effects on any designated sites because of the Proposed Development	No		
Habitats and Flora					
Hedgerows (WL1)	Local importance	Comprises native hedgerow species and provides suitable nesting	Yes		

		and foraging habitat for a range of species. Sections of the hedgerow along northern and western extents of this habitat will be retained. However, this habitat may be indirectly affected by the Proposed Development through dust deposition or root damage.	
Flower beds and borders (BC4)	Less than local importance	This habitat is man- made and comprises of ornamental floral planting and is restricted in extent to a small insignificant area on the Site. The loss of this low value habitat will not be of significance.	No
Treeline (WL2)	Less than local importance	The treeline is comprised of non-native species and is restricted in extent to a small insignificant area on the Site. The loss of this low value habitat will not be significant.	No
Buildings and artificial surfaces (BL3)	Less than local importance	This habitat is man-man and of little to no value.	No
Dry Meadows and grassy verges	Less than local importance	The loss of this low value habitat will not be of significance. This habitat type is also abundant in the wider area.	No
(Mixed) broadleaved woodland (MWD1)	Local Importance	Comprises of native tree species and provides suitable nesting and foraging habitat for a range of species. This stretch of the habitat will be retained as these trees have been plated as roadside trees for the existing carriageway that runs above the eastern section of the Site. Therefore, this habitat can be indirectly affected by the Proposed Development	Yes

		through dust deposition or root damage.	
Amenity grassland (GA2)	Less than local importance	The loss of this low value habitat will not be significant.	No
Spoil and bare ground (ED2)	Less than local importance	The loss of this species deficient habitat will not be significant.	No
Recolonising bare ground (ED3)	Less than local importance	This habitat is species poor and is also abundant in the wider area. Therefore, the loss of this low value habitat will not be significant.	No
Invasive species	Less than local importance	The loss of these low value invasive species is not considered to be significant.	No
	Fau	una	
Bats	Roosting: Less than local importance	PRF-I potential for trees and No potential for buildings for roosting bats, and moderate suitability for commuting and foraging bats. Details of abundance and species	
	Bats Commuting and foraging: Local importance	diversity of bats for the site will be confirmed after the required bat surveys to be conducted for the Site are complete. Bat species utilising the Site have the potential to be significantly affected by the Proposed Development in the absence of mitigation.	Yes
Birds	Local importance	One amber listed and several green listed bird species were recorded at the Site with suitable breeding habitats for a few notable species. Details of the species diversity of birds for the Site will be confirmed after the required bird	Yes

		surveys to be conducted for the Site are complete. Bird species utilising the Site have the potential to be significantly affected by the Proposed Development in the absence of mitigation.	
Large Mammals	Less than local importance	No resting sites, foraging or commuting habitats for mammals such as badger or otter were identified at the Site. Therefore, it is presumed that the Site is not of importance to these species	No
Small Mammals (excl. bats)	Local Importance	Suitable habitats present for some of the small native mammals, such as hedgehog, pygmy shrew, and wood mouse at the Site, which may be more timid and less likely to be recorded during surveys. Hedgehog specifically hibernate and may be susceptible to injury during vegetation clearance during hibernation in the absence of mitigation.	Yes
Common Lizard	Local Importance	Some suitable habitats in the form of existing waste material such as concrete blocks, and hedgerows, woodlands, trees and grassland habitats at the Site may provide basking and refugia spots. No desk study records but this species is widespread throughout Ireland and thus presumed present.	Yes
Fish, amphibian and other aquatic species	Less than local importance	No watercourses or waterbodies are located at the Site of the Proposed Development. Therefore, there are no	No

suitable habitats for fish,	
amphibians, and other	
aquatic species at the	
Site and the impacts to	
these species will	
negligible.	

6.4.2.3 Operational Stage

The impacts of the Operational Phase of the Proposed Development at Plot 2 (St. Mochta's LRD) on the identified KERs have been assessed, and Table 6.28 below summaries the evaluation rating assigned to each ecological feature and the rationale behind these evaluations is also provided.

Table 6.28: Evaluation of designated sites, habitats, flora and fauna recorded within the Site for the Operational Phase of Plot 2 (St. Mochta's LRD). Those identified as Key Ecological Receptors (KERs) are highlighted in green

Species / Species Group	Evaluation	Rationale	Key Ecological Receptor (KER)	
	Habitats	and Flora		
Hedgerows (WL1)	Local importance	Sections of the native hedgerows along the western and northern boundaries of the Site will be retained. While this habitat provides suitable nesting and foraging habitats for a range of bird species, and commuting bat species, the hedgerows along the Site will be enhanced via tree planting as per the landscape design for the Operational Phase of the Proposed Development. Therefore, the positive impact will act to offset some of the negative impacts from the loss of this habitat.	Yes	
Flower beds and borders (BC4)	Less than local importance	The loss of this low value habitat will not be significant given the wildflower meadows proposed for the Operational Phase of the Proposed Development per the landscape design.	No	
Treeline (WL2)	Less than local importance	The loss of this low value habitat will not be	No	

STEPHEN LITTLE & ASSOCIATES MAY 2025

		significant given the woodland and street tree plantation proposed for the Operational Phase of the Proposed Development as per the landscape design.	
Buildings and artificial surfaces (BL3)	Less than local importance	The loss of this habitat will not be significant given the woodland and street tree plantation proposed for the Operational Phase of the Proposed Development as per the landscape design	No
Dry meadow and grassy verges (GS2)	Less than local importance	The loss of this low value habitat will not be significant given the hedgerow, street tree, woodland, scrub and wildflower meadows that is proposed for the Operational Phase of the Proposed Development as per the landscape design.	No
(Mixed) broadleaved woodland (MWD1)	Local Importance	This habitat is connected to the Site along the eastern boundary. Although it is to be retained, it may be affected by the Proposed Development through direct damage or root damage during the Operational Phase of the Proposed Development.	Yes
Spoil and bare ground (ED2)	Less than local importance	The loss of this habitat will not be significant and will be further enhanced by the proposed biodiverse green spaces for the Operational Phase of the Proposed Development.	No
Recolonising bare ground (ED3)	Less than local importance	The loss of this low value habitat will not be significant and will be further enhanced by the proposed biodiverse	No

Amenity grassland (GA2)	Less than local importance	No	
	Roosting: Less than local importance		
Bats	Commuting and foraging: Local importance	commuting corridors. However, the bat friendly lighting measures in line with the Bat Conservation Trust guidelines on artificial lighting and bats has been incorporated into the lighting design plan. Therefore, the positive impact will act to offset	Yes
Birds	Local Importance	some of the negative impacts from the loss of habitats for bats. Although negative impacts are envisaged due to the loss of suitable breeding habitats for bird species, the planting of street trees, woodlands, scrub and enhancement of hedgerows for the Operational Phase of the Proposed Development will provide a positive impact on bird species. Likelihood of Collision	Yes

		While the physical location of buildings and structures can influence the likelihood of bird collisions, the Site itself is located within a combination of urban and agricultural lands and is not deemed to be located in a sensitive area in terms of bird flight paths i.e., it is not located along the coast, or adjacent to any SPAs designated for wetland bird populations.	
		Building Height The Proposed Development entails the construction of low-level residential buildings and as such, the risk of migrating birds colliding with the structure due to its height is deemed to be negligible Building Appearance	
		The overall façades of the proposed buildings are well broken up, with a varied material composition interspersing any reflective areas. These architectural design features provide important visible cues as to the presence and extent of the proposed structures to any commuting/foraging bird species should they be in the vicinity of the Site.	
Large Mammals	Less than local importance	No resting sites, foraging or commuting habitats for mammals such as badger or otter were identified at the Site. Therefore, it is deemed that the Site will have negligible impact on the habitats of large	No

		mammals during the Operational Phase of the Proposed Development.	
Small Mammals (excl. bats)	Local Importance	Noise, increase in light, and potential physical disturbance due to increased human presence associated with the Operational Phase has the potential to cause a negative, permanent, moderate impact to small mammals in the absence of suitable mitigation. The Proposed Development will also result in a loss of foraging and commuting habitat for small mammals, however due to the extent of the surrounding suitable habitat in the vicinity of the Site, and considering the new green spaces proposed for installation at the Site, these factors have the potential to cause a negative, permanent, slight impact to small mammals.	Yes
Common Lizard	Local Importance	No significant impacts on lizards are anticipated during the Operational Phase. The proposed planting at the Site has the potential to provide a positive, permanent, slight impact. Further consideration of this will be provided once the final planting plans are prepared.	Yes
Fish, amphibian and other aquatic species	Less than local importance	Impacts on fishes, amphibians and other aquatic species is not envisaged due to the lack of water courses at the Site and the proposed SuDS measures that have	No

been incorporated into the landscape design for	
the Operation Phase of	
the Proposed	
Development	

6.4.2.4 Do-Nothing Impact

Under the do-nothing scenario, most of the habitats at the Site of the Proposed Development would continue to undergo succession. The construction works for the Strategic Housing Development (ABP-312318-21) adjacent to the Site has already commenced and will significantly impact the dry meadows habitats (GS2) habitat along the southern section of the Site. The construction of the aforementioned development will not result in a change in habitat connectivity south of the Site due to the lack of green corridors in these areas.

The other remaining hedgerows would continue to serve as biodiversity corridors, providing habitat connectivity, along with nesting/roosting and foraging habitat for birds and mammals. The grassland would also continue to provide foraging and commuting habitat for local wildlife and pollinators, with potential for scrub species along the hedgerow to further encroach into the grassland area. The floral composition of recolonising bare ground habitats will continue to increase in the absence of disturbance, further encroaching into the neighbouring bare ground habitats. In the absence of regular maintenance and/or management, the amenity grasslands have the potential to support tall swathes of grasses, as well as floral species found at the bases of the adjacent hedgerow and recolonising grounds.

6.5 Mitigation Measures (Ameliorative, Remedial or Reductive Measures)

Given that the recommended mitigation measures are appropriate for both Plot 1 (Luttrellstown Gate Phase 2) and Plot 2 (St. Mochta's LRD) of the Site of the Proposed Development, the following measures will apply to both plots unless otherwise state. Where a mitigation measure pertains exclusively to one plot, this will be explicitly identified.

Please note: A Site-specific approach that takes into consideration the biodiversity assemblage recorded at the Site will be incorporated into the recommended mitigation on completion of the full suite of ecological surveys. Therefore, the mitigation and biodiversity enhancement outlined below may be superseded upon completion of the full suite of ecological surveys at the Site.

6.5.1.1 Construction Stage

6.5.1.1.1 Protection of Habitats and Designated Sites

6.5.1.1.1.1 Mitigation 1: Tree Protection

Protective tree fencing in compliance with BS 5837:2012 'Trees in relation to design, demolition and construction – Recommendations' will be erected prior to any Construction works being undertaken to prevent damage to the canopy and root protection areas of existing trees at the Site. The fencing will be signed off by a qualified arborist prior to Construction to ensure it has been properly erected. No ground clearance, earthworks, stockpiling or machinery movement will be undertaken within these areas.

6.5.1.1.1.2 Mitigation 2: Standard Surface water and ground water protection measures

6.5.1.1.1.2.1 Control of Fuel and Chemical Storage

The storage and use of fuel and oils will be kept to a minimum at the Site.

If small quantities of oils and chemicals oils are required at the Site, the use of these will be strictly controlled in accordance with procedures outlined in the CEMP and storage will be avoided where possible. All tank, container and drum storage areas shall be rendered impervious to the materials stored therein. Bunds and storage areas shall be designed having regard to Environmental Protection Agency guidelines 'Storage and Transfer of Materials for Scheduled Activities' (EPA, 2004) and Enterprise Ireland Best Practice Guidelines (BPGCS005). All tank and drum storage areas shall, as a minimum, be bunded to a volume not less than the greater of the following:

- 110% of the capacity of the largest tank or drum within the bunded area; or
- 25% of the total volume of substance that could be stored within the bunded area.

Any fuels retained on drip trays, mobile bunds, etc., will be emptied into a secure bunded waste oil drum to await appropriate disposal offsite.

Refueling of plant during the Construction Phase will be carried out in accordance with standard best practice. Refueling will only be carried out at the designated, impermeable refueling station location onsite with appropriate containment in place. This station will be fully equipped for spill response and a specially trained and dedicated Environmental and Emergency Spill Response Team will be appointed before the commencement of works at the Proposed Development Site.

Where possible any oil and lubricant changes and maintenance will take place offsite. Only emergency breakdown maintenance will be carried out on Site. Drip trays and spill kits will be available on Site to ensure that any spills from vehicles are contained and removed offsite.

All personnel working onsite will be trained in pollution incident control response. Emergency silt control & spillage response procedures contained within the CEMP will ensure that appropriate information will be available on site outlining the spillage response procedures and a contingency plan to contain silt during an incident.

Provided that these requirements are adhered to, and site crew are trained in the appropriate refueling techniques, it is not expected that there will be any fuel/oil wastage at the Site.

6.5.1.1.1.2.2 Control of Emissions to Surface water and Drainage

Works carried out as part of the Proposed Development will comply with all Statutory Legislation including the Local Government (Water Pollution) acts, 1977 and 1990.

Silt traps, and silt fences will be provided by the contractor where necessary to prevent silts and soils being washed away by heavy rains during the course of the Construction Phase. Surface water runoff and water pumped from the excavation works will be discharged via a silt trap / settlement pond to the existing foul drainage network.

In addition, the following general measures will be undertaken:

- Where required, designated impermeable cement washout areas will be provided.
- Run-off from the working site or any areas of exposed soil will be channeled and intercepted at regular intervals for discharge to silt-traps or lagoons with over-flows directed to land rather than to a drain.
- Silty water generated on Site will be treated using silt traps/settlement ponds and temporary interceptors and traps will be installed until such time as permanent facilities are constructed.
- Storm drain inlets which could receive stormwater from the project will be protected throughout the Construction Phase.
- A regular review of weather forecasts of heavy rainfall will be conducted, and a contingency plan will be prepared for before and after such events to minimise any potential nuisances. As the risk of the break-out of silt laden run-off is higher during these weather conditions, no work will be carried out during such periods where possible.
- Any imported materials will, as much as possible, be placed on Site in their proposed location and double handling will be avoided. Where this is not possible designated temporary material storage areas will be used.

- These temporary storage areas will be surrounded with silt fencing to filter out any suspended solids from surface water arising from these materials.
- Temporary hydrocarbon interceptor facilities will be installed and maintained where Site works involve the discharge of drainage waters to nearby drains.
- All containment and treatment facilities will be regularly inspected and maintained.
- All personnel working on site will be trained in pollution incident control response.
- If portaloos and/ or containerised toilets and welfare units will be used to provide facilities for site personnel, all associated waste will be removed from site by a licensed waste disposal contractor.

Under no circumstances will any untreated wastewater generated onsite (from equipment washing, road sweeping etc.) be released into nearby drains.

6.5.1.1.1.2.3 <u>Control of Emissions to Soil and Groundwater</u>

Measures set out in the previous section also serve to protect soil and groundwater. In addition, the following measures will also be undertaken:

- No direct untreated point discharge of construction runoff to groundwater will be permitted.
- Where a pollution incident is detected, construction works will be stopped until the source of the construction pollution has been identified and remedied.
- Groundwater may be encountered during the construction works. Where water must be pumped from the excavations, water will be managed in accordance with best practice standards (i.e., CIRIA – C750) and regulatory consents.
- Any excavated and potentially contaminated stockpiled soils will be constructed/ located/ sheeted in a manner that ensures water is contained within the Site boundary.

6.5.1.1.1.3 Mitigation 3: Reduction of dust related impacts

The following general dust control measures will be followed for the duration of the Construction Phase of the Proposed Development and will ensure no significant dust related impacts occur to nearby sensitive receptors such as the Royal Canal located north of the Site of the Proposed Development.

- Haulage vehicles transporting gravel and other similar materials to Site will be covered by a tarpaulin or similar.
- Access and exit of vehicles will be restricted to certain access/exit points.
- Vehicle speed restrictions of 20km/hr will be in place.
- Bowsers will be available during periods of dry weather throughout the Construction period.
- During dry and windy periods, and when there is a likelihood of dust nuisance, a bowser will operate
 to ensure moisture content is high enough to increase the stability of the soil thereby reducing the
 amount of dust.
- Stockpiling of imported materials will be avoided where possible with imported materials ideally placed on Site in their proposed location upon receipt with double handling avoided.
- Stockpiles will be stored in sheltered areas of the Site, covered, and watered regularly or as needed if exposed during dry weather.
- Gravel should be used at Site exit points to remove caked-on dirt from tyre tracks.
- Hard surfaced roads will be wet swept to remove any deposited materials.
- Unsurfaced roads will be restricted to essential traffic only.
- If required to control dust nuisance wheel-washing facilities will be located at the exit from the construction area.
- Dust production as a result of Site activity will be minimised by regular cleaning of the access roads using vacuum road sweepers and washers. Access roads should be cleaned at least 0.5km on either side of the approach roads to the access points.
- Public roads outside the Site shall be regularly inspected for cleanliness, as a minimum daily, and cleaned as necessary. A road sweeper will be made available to ensure that public roads are kept free of debris.
- The frequency of cleaning will be determined by the Site agent and is weather and activity dependent.

- The height of stockpiles will be kept to a minimum and slopes should be gentle to avoid windblown soil dust.
- The following will be dampened during dry weather:
- o Unpaved areas subject to traffic and wind.
- Stockpiles.
- Areas where there will be loading and unloading of dust-generating materials.
- Under no circumstances will wastewater from equipment, wheel or surface cleaning enter the drainage ditches along the boundaries of the Site.

6.5.1.1.1.4 Mitigation 4: Invasive Species Removal (specific to Plot 2 (St. Mochta's LRD)

It is recommended that non-native/invasive flora species recorded at the Site are controlled/removed as per the appropriate best-practice guidelines. Removal and disposal should be carried out in accordance with appropriate guidelines such as TII (formerly NRA) *The Management of Invasive Alien Plant Species on National Roads* (2020), with consideration given to the prevention of spread of these plants.

<u>Recommended Management:</u> Physical removal and off-site disposal of butterfly-bush is recommended where it occurs within the survey area.

6.5.1.1.2 Protection of Fauna

6.5.1.1.2.1 Mitigation 5: Reduction of Noise Related Impacts

Noise generated during the Construction Phase of the Proposed Development could cause temporary disturbance to a number of faunal species in the vicinity of the Site. To mitigate this disturbance, the following measures will be implemented:

- Selection of plant with low inherent potential for generating noise.
- Siting of plant as far away from sensitive receptors as permitted by site constraints.
- Avoidance of unnecessary revving of engines and switch off plant items when not required.
- Keep plant machinery and vehicles adequately maintained and serviced.
- Proper balancing of plant items with rotating parts.
- Keep internal routes well maintained and avoid steep gradients.
- Minimise drop heights for materials or ensure a resilient material underlies.
- Use of alternative reversing alarm systems on plant machinery.
- Where noise originates from resonating body panels and cover plates, additional stiffening ribs or materials should be safely applied where appropriate.
- Limiting the hours during which Site activities likely to create high levels of noise are permitted.
- Appointing a site representative responsible for matters relating to noise.
- Monitoring typical levels of noise during critical periods and at sensitive locations.

These measures will ensure that any noise disturbance to nesting birds or any other fauna species in the vicinity of the Site will be reduced to a minimum.

6.5.1.1.2.2 Mitigation 6: Construction Phase Lighting

The full suite of bat surveys for both plots of the Site are not yet complete, therefore a precautionary approach will be taken. The following mitigation measures are more general and not specific to the bat activity present at the Site and may change following completion of the bat transect surveys.

As a precautionary measure, no overnight lighting will be directed to the natural habitats bounding the Site. Where overnight lighting cannot be avoided in these areas due to health and safety concerns, the lighting within the Proposed Development will be designed and installed to minimise the impact on local wildlife as agreed with the Ecologist and in accordance with the Bat Conservation Trust guidelines on artificial lighting and bats (Collins, 2023)

There will be no light spill to the boundary habitats.

- All luminaires used will lack UV/IR elements to reduce impact.
- LED luminaires will be used due to the fact that they are highly directional, lower intensity, good colour rendition and dimming capability.
- A warm white spectrum (3000 Kelvins will be used to reduce the blue light component of the LED spectrum).
- Luminaires will feature peak wavelengths higher than 550nm to avoid the component of light most disturbing to bats.
- Column heights should be carefully considered to minimise light spill. The shortest column height allowed should be used where possible.
- Only luminaires with an upward light ratio of 0% and with good optical control will be used.
- Luminaires will be mounted on the horizontal, i.e., with no upward tilt.
- Any external security lighting will be set on motion-sensors and short (1min) timers.
- As a last resort, accessories such as baffles, hoods or louvres will be used to reduce light spill and direct it only to where it is needed.

6.5.1.1.2.3 Mitigation 7: Vegetation Clerance

Vegetation clearance of the hedgerows interlaced with trees, and grassland habitats for Plot 1 (Luttrellstown Gate Phase 2), and hedgerow, treeline, grassland and woodland habitats for Plot 2 (St. Mochta's LRD) will need to be cognisant of any potentially present fauna. Table 6.29 provides guidance for when vegetation clearance is permissible in relation to wintering, hibernating and breeding fauna. Information sources include British Hedgehog Preservation Society's *Hedgehogs and Development* and *The Wildlife (Amendment) Act, 2000*. The preferred period for vegetation clearance is within the months of September and October to avoid the main breeding bird season and bat maternity and roosting season as well as mammal hibernation.

Where this seasonal restriction cannot be observed, a check for active nests, will be carried out immediately prior to any Site clearance by an Ecological Clerk of Works (ECoW) and repeated as required to ensure compliance with legislative requirements. Where a breeding bird and an active nest is found, the nest will be protected, and no further works will take place in the vicinity of the nest until the young have fledged.

Table 6.29: Seasonal restriction on vegetation removal. Red boxes indicate periods when clearance/works are not advised

Ecological Features	Jan	Feb	March	April	May	June	July	Aug	Sept	Oct	Nov	Dec
Breeding birds	s clearance r				Nesting bird season clearance of vegetation or works to levant structures permitted unless ned to be devoid of nesting birds by an ecologist					Vegetation clearance permissible		
Hibernating mammals (namely hedgehog)	No veget to rele per cor devoid	seasor clearan tation or evant str mitted u	ce of works ructures inless to be ernating by an		Veg	etatio cle	earance	permiss	sible			arance of sation rks to vant tures witted ess med to void of

Common lizard

No habitat clearance permissible

Lizard hibernation
Season

Habitat (scrub, tall sward grass) clearance permissible

No habitat clearance permissible

Additionally, all vegetation clearance will be carried out in sections working in a consistent direction to prevent entrapment of protected fauna potentially present (e.g., hedgehog, pygmy shrew). Logs and branches from this vegetation will be utilised for the creation of hibernacula on Site, see section 6.5.2.5 below. A phased cutting approach under the supervision of a suitably qualified ECoW will be used to allow wildlife (small mammals, reptiles and amphibians) to move away from any suitable habitat that will be removed:

- Phase 1 Cutting vegetation to 150-200 mm and removing the arisings;
- Phase 2 After a minimum of one hour, hand-searching the cut areas (conducted by an ECoW) and removing any sheltering habitat (e.g. logs or debris) then cutting vegetation to ground level and removing the arisings; and
- Phase 3 Soil scrape.

Should any suitable refugia or day nesting habitats need to be removed, this will be carried out outside the most vulnerable breeding periods for hedgehogs wherever practicable (main hedgehog birthing months June and July) and will be supervised by the ECoW.

6.5.1.1.2.4 Mitigation 8: Waste Management

As best-practice, all construction-related rubbish on-site e.g., plastic sheeting, netting etc. should be kept in a designated area on-site and kept off ground level so as to protect small fauna (such as small mammals, amphibians and reptiles) from entrapment and death.

6.5.1.1.2.5 Mitigation 9: Avoidance of accidental trapping of fauna

In order to avoid accidental harm/injury or mortality to mammals during construction all excavations shall have a wooden plank, sloping edge or other means of escape to avoid accidental trapping of mammals. All pipes shall be covered at night.

6.5.1.2 Operational Stage

6.5.1.2.1 Habitats and Flora

6.5.1.2.1.1 Mitigation 10: Invasive Species Management

Certain plant species and their hybrids are listed as Invasive Alien Plant Species in Part 1 of the Third Schedule of the European Communities (Birds and Natural Habitats) Regulations 2011 (SI 477 of 2011, as amended). In addition, soils and other material containing such invasive plant material, are classified in Part 3 of the Third Schedule as vector materials and are subject to the same strict legal controls.

As such, it is recommended that any newly landscaped areas, particularly where infill materials and soils have been imported for soft landscaping, are assessed during the Operational Phase within the next botanical season for the presence of any inadvertently introduced invasive species, with particular focus on those listed on Schedule III of SI 477 of 2011. If invasive species are detected, an Invasive Species Management Plan will be prepared, agreed with the Local Authority and implemented at the earliest possibility to limit the potential for further spread.

6.5.1.2.1.2 Mitigation 11: Bats

In accordance with the best practise bat-friendly lighting guidelines (ILP, 2023), the below measures will be incorporated as part of the Lighting Design of the Proposed Development:

- All luminaires should lack UV elements when manufactured. Metal halide, compact fluorescent sources should not be used.
- LED luminaires should be used where possible due to their sharp cut-off, lower intensity, good colour rendition and dimming capability.
- A warm white light source (3000 Kelvin or lower) should be adopted to reduce blue light component.
- Light sources should feature peak wavelengths higher than 550nm to avoid the component of light most disturbing to bats.
- Internal luminaires can be recessed where installed in proximity to windows to reduce glare and light spill.
- Column heights should be carefully considered to minimise light spill and glare visibility. This should be balanced with the potential for increased numbers of columns and upward light reflectance as with bollards.
- Only luminaires with a negligible or zero Upward Light Ratio, and with good optical control, should be considered.
- Luminaires should always be mounted horizontally, with no light output above 90° and/or no upward tilt.
- Where appropriate, external security lighting should be set on motion sensors and set to as short a possible a timer as the risk assessment will allow. For most general residential purposes, a 1 or 2 minute timer is likely to be appropriate.
- Only if all other options have been explored, accessories such as baffles, hoods or louvres can be used to reduce light spill and direct it only to where it is needed. However, due to the lensing and fine cutoff control of the beam inherent in modern LED luminaires, the effect of cowls and baffles is often far less than anticipated and so should not be relied upon solely.

6.5.2 Biodiversity Enhancement Measures

Biodiversity enhancement measures for both plots have been included in this section.

6.5.2.1 Biodiversity Enhancement by Design

The Landscape Plans for the respective plots of the Site of the Proposed Development incorporates native planting throughout the open green spaces of the Proposed Development. This will take the form of street tree planting, mixed woodland planting, hedgerows, scrub beds, and wildflower grass meadows. The planting schedule will be informed prior to the commencement of the construction phase and will be agreed with inputs by a qualified ecologist. A more general planting plan have been included in the Landscape Plans for the respective plots, which detail the specifications for plant material, the requirements of the Landscape contractor, and proposals for monitoring establishment of green spaces across both plots. The proposed Landscape Plan for both plots of the Site have been designed to enhance biodiversity by introducing a greater variety of habitats than those that are currently present on Site.

6.5.2.2 Enhancement 1: Hedgehog Highways

By creating a number of separate private dwellings and gardens at a Site, the land becomes fragmented and largely inaccessible to species such as hedgehog, which like to roam each night in search of food (garden pests e.g., slugs). This can easily be fixed by ensuring that the boundaries and barriers within and surrounding the Site i.e., garden fencing, railings and gates, are permeable for hedgehogs, as seen in Figure 6.12. This can be achieved by:

- The use of fence panels with 13 x 13 cm holes at ground level (Hedgehog holes);
- Leaving a sufficient gap beneath gates, and;
- Leaving brick spaces at the base of brick walls.



Figure 6.12: Examples of Hedgehog highways' that can maintain habitat connectivity for hedgehogs in residential developments

The inclusion of hedgehog highways is recommended as part of the landscape design of both plots of the Site, specifically along the public open spaces proposed along the boundaries of each of the two plots. A variety of fence suppliers' stock specific hedgehog-friendly fencing options, which can be easily incorporated at little or no additional cost. These simple measures will provide habitat connectivity at the Site for hedgehogs and reduce the impact of the land-use change on this species.

Including details of hedgehog-friendly features in the new homeowner's welcome pack will raise awareness and prevent homeowners from reversing these features, for instance blocking fence holes.

6.5.2.3 Enhancement 2: Pollinator Habitat

Pollinator/'insect habitat, as seen in Figure 6.13, will be created on both plots of the Site by:

- Creating an earth bank.
- Scraping back some bare earth.
- Leaving some areas to grow wild, and/or
- By drilling holes 10cm deep in unvarnished wood for solitary bees.



Figure 6.13: Example of solitary bee habitat. Extracted from How-To-Guide: Creating Wild Pollinator Nesting Habitat (NBDC, 2016)

Large bee or insect hotels will not be installed. Guidance from the All -Ireland Pollinator Plan states "Don't install a large bee or insect hotel. Large bee hotels are attractive to humans, but not great for pollinators. They can encourage the spread of disease and attract predators. Avoid anything bigger than an average-sized bird box. There are many other ways to provide nesting habitats for pollinators, such as providing wild areas of undisturbed long grass, and scraping back some bare earth. If you want to make a bee hotel, make sure it is small, and position it away from bird feeders so the insects aren't

easy targets." A link to a "How-to-guide Creating wild pollinator nesting habitat" is provided for the development management company to put these habitats in place: Pollinator-Nesting-How-to-Guide-2022-WEB.pdf (pollinators.ie). An appointed ecologist will oversee the creation of these habitats.

6.5.2.4 Enchantment 3: Bat Boxes

Four summer bat boxes (e.g., Woodcrete 1FF design) will be erected on each of the two plots on the Site of the Proposed Development. The number of boxes may increase should the activity surveys find evidence of roosting on Site to mitigate any loss of roost habitat. The boxes will be installed as part of the landscaping works, so as to not delay their deployment and potential positive impacts.

Bat boxes will be sited carefully, and this will be undertaken by a bat specialist. The bat ecologist will denote the locations, orientation and height of the bat boxes to be erected with assistance from the contractor. Some general points that will be followed include:

- Bat boxes will be erected on trees (or telegraph poles) with no crowding branches or other obstructions for at least 1 metre above and below the bat box.
- The diameter of the tree should be wide and strong enough to hold the required number of boxes.
- Locate bat boxes in areas where bats are known to forage or adjacent to suitable foraging areas.
 Locations will be sheltered from prevailing winds.
- Bat boxes will be erected at a height of 4-5 metres to reduce the potential for vandalism and predation of roosting bats.
- The recommended Woodcrete 1FF design is open at the bottom, allowing the droppings to fall out, and so does not need cleaning.

6.5.2.5 Enhancement 4: Hibernacula

It is recommended to enhance the landscaped areas for small mammals, amphibians and reptiles by providing hibernacula in the form of log and brush piles within both plots of the Site of the Proposed Development. It is recommended that 2-3 areas of hibernacula are provided at areas furthest removed from likely human activity.

In the case of plot 1 (Luttrellstown Gate Phase 2), the northeast corner and southwest corner of the Site will be suitable areas for the installation of the hibernacula, whereas for plot 2 (St. Mochta's LRD), the public open spaces along the eastern boundary, but away from the pedestrian and cycle lane, will be suitable areas.

Hibernacula for hedgehogs, amphibians and reptiles is relatively easy to create from logs and soil, all of which can likely be sourced from the Site during works. Wood in various sizes should be piled either in a shallow depression or on the slope of the attenuation pond in a disorganised way to create nooks and crevices. Larger tree trunks or rocks should be placed so that they will protrude through the final mound to provide open entrances to the mound. This pile should then be covered in soil to allow the inner crevices to maintain a stable temperature through the winter and allow for hibernation.

6.5.2.6 Enhancement 5: Swift Boxes/Bricks

The installation of swift bricks/boxes is recommended for both plots of the Site of the Proposed Development. Swifts (*Apus apus*) are an endangered species of bird that migrate to Ireland from South Africa each summer and traditionally nest in crevices or the eaves of buildings. The swift bricks in particular are discrete hollow bricks designed to building regulation standards that can be matched to the design of the façade.

Swifts are a "clean" bird species which remove their own wastes from their nests periodically. As such, Swift bricks do not require any cleaning by the management company.

The incorporation of Swift Boxes or Bricks will help recover the declining swift population, which are now Red Listed in Ireland (Gilbert et al., 2021). The following recommendations are extracted from "Saving Swifts" by Birdwatch Ireland (BirdWatch Ireland, 2023).

Swift Bricks/boxes:

- should be constructed of long-lasting material and securely fixed in position.
- should be erected at least five metres above ground level.
- should be erected in sheltered cool areas out of the sun, or under an overhang and /or under the eaves. Bricks can be placed at any aspect, however, as they tend not to overheat the way that externally fitted boxes can.
- should have a clear airspace in front for access.
- should be grouped (side by side in rows) as swifts are colony nesters.
- should avoid sites which can be accessed by predators- cats, squirrels, magpies, rats.
- should avoid sites near plate glass windows because they are a known collision hazard for birds.
- should not be placed directly above ledges or other obstructions. Swifts drop before taking flight and can collide with obstacles below the nest entrance.
- should not be one above the other.
- should not be near spotlights or later fit spotlights near them

6.5.2.7 Enhancement 6: Long Term Management of Hedgerows

For the long term management of hedgerows during the Operational Phase at both plots (Plot 1 - Luttrellstown Gate Phase 2, and Plot 2 - St. Mochta's LRD) of the Proposed Development, relevant guidance has been sourced from Hedgerows Ireland (HE, 2025), and (LAHO, 2016), to inform best practice and optimal enhancement of hedgerows at Plot 1 and plot 2 of the Site.

As per the guidance provided in Hedgerows Ireland (HE,2025), it is recommended that cutting/flailing of hedgerows is not undertaken annually. This is because annual cutting has been associated with reducing local biodiversity benefits that the hedgerows may offer to flowering species within the hedgerow itself, as well as the pollinators that rely on these floral species. Furthermore, the annual cutting of hedgerows can also diminish food resources in the form of berries or fruits for birds thereby depleting resources that the bird species may rely on. Cutting can also directly impact the nesting behaviour of birds in the locality, therefore, all cutting mush take place outside of the breeding bird season (March to August).

Additionally, as per (LAHO, 2016), it is recommended that proper maintenance of hedgerows should be established to encourage flowering, fruiting and growth to boost wildlife potential in hedgerows. This is to be accomplished by ensuring that mature hedgerows are in good condition and must be allowed to grow naturally, and maintenance is confided to essential practices such as stockproofing, inplanting, and the control of invasive species. Weak hedgerows, which have lost their vigour, will require more intervention such as laying or coppicing. Any established hedgerows will need cutting every two to three years, and the maintenance is to be done on a rotational basis around the Site to ensure that there is growth at all stages.

6.6 Residual Impact of the Proposed Development

The residual impacts are the same for Plot 1 (Luttrellstown Gate Phase 2), Plot 2 (St. Mochta's LRD) and the cumulative of both Sites of the Proposed Development. Therefore, Table 6.30 below outlines information for all three aspects of the Proposed Development.

Residual impacts are defined as 'effects that are predicted to remain after all assessments and mitigation measures'. They are the remaining 'environmental costs' of a project and are the final or intended effects of a development after mitigation measures have been applied to avoid or reduce adverse impacts. Potential residual impacts from the proposed development were considered as part of this environmental assessment. Table 6.30 below provides a summary of the impact assessment for the identified KERs and details the nature of the impacts identified, mitigation proposed and the classification of any residual impacts.

All mitigation measures detailed in this Chapter will be implemented in full and will remain effective throughout the lifetime of the facility. Therefore, no significant negative residual impacts on the local ecology or on any designated nature conservation sites will result from the Proposed Development.

ENVIRONMENTAL IMPACT ASSESSMENT REPORT KELLYSTOWN

Table 6.30: Summary of potential impacts on KER(s), mitigation measure/mitigating factors and residual impacts for Plot 1 (Luttrellstown Gate Phase 2), Plot 2 (St. Mochta's LRD), and the cumulative of both plots.

Key Ecological	Level of	Level of Potential		Impact without mitigation				Proposed			
Resources			Quality	Magnitude /Extent	Duration	Significance	mitigation / mitigation factors	enhancements (if any)	Residual impact		
	Designated Sites										
Royal Canal National pNHA (002103) Importance	National Importance	Construction Phase: Weak potential for deterioration of water quality and resources leading to alteration of habitat and species fragmentation.	Negative	National	Short-term	Minor (slight or moderate)	Mitigation 2: Standard surface water and ground water	None	Imperceptible		
		Operational Phase: None Envisaged	None	None	None	None	protection measures		Imperceptible		

Key Ecological	Level of	Potential Impact	Impact without mitigation				mitigation /	Proposed	
Resources	Significance		Quality	Magnitude /Extent	Duration	Significance	mitigation factors	enhancements (if any)	Residual impact
					Habitats				
(Plot 1)		Construction Phase: Loss of habitat	Negative	Local	Permanent	Minor (neutral or slight)	Mitigation 1: Tree Protection Mitigation 7: Vegetation	Recommend planting of native	Negative, Local,
Hedgerows (WL1)	Local importance		None	None	None	None	Clearance Enhancement 6: Long term Management of Hedgerows	hedgerow, shrub, woodland species within the Site	Permanent, Neutral or Slight
(Plot 2) Hedgerows (WL1), and	Hedgerows (WL1), and Local	Construction Phase: Loss of habitat	Negative	Local	Permanent	Minor (neutral or slight)	Mitigation 1: Tree Protection Mitigation 7:	Recommend planting of native hedgerow, shrub,	Negative, Local, Permanent,
(mixed) important broadleaved woodland (MWD1).	importance	Operational Phase: None identified	None	None	None	None	Vegetation Clearance	woodland species within the Site	Neutral or Slight
Invasive Species (Plot 2)	Less than local importance	Construction Phase: Spread of invasive species.	Negative	Local	Short-term	Minor (neutral or slight)	Mitigation 4: Invasive Species Removal	None	Imperceptible

Key Ecological	Level of	of Potential	Impact without mitigation				Proposed Proposed	Proposed	
Resources		Impact	Quality	Magnitude /Extent	Duration	Significance	mitigation factors	enhancements (if any)	Residual impact
		Operational Phase: Spread of invasive species.	Negative	Local	Short-term	Minor (neutral or slight)	Mitigation 10: Invasive species management		
					Fauna				
		Construction Phase: Loss of habitat due to felling of the sections of	Negative		Permanent		Mitigation 6: Construction Phase Lighting		
Bat Assemblage	Local Importance	hedgerows. Increase in lighting during construction works.	Negative	To be confirmed on completion of surveys	Short-term	To be confirmed on completion of surveys	Mitigation 5: Reduction of Noise Related Impacts	Enhancement 3: Bat boxes	To be confirmed on completion of surveys
		Operational Phase: Increase lighting.	Negative		Permanent		Mitigation 12: Bats		

Key Ecological	Level of	evel of Potential		Impact with	out mitigatio	n	Proposed mitigation /	Proposed enhancements (if any)	
Resources	Significance	Impact	Quality	Magnitude /Extent	Duration	Significance	mitigation / mitigation factors		Residual impact
Bird Assemblages	Local Importance	Construction Phase: Habitat loss. Disturbance from noise, dust and/or lighting. Risk of injury or death during vegetation clearance Operational Phase: Additional habitat as a result of the proposed planting on Site.	Negative Negative Positive	To be confirmed on completion of surveys	Permanent Short-term Permanent	To be confirmed on completion of surveys	Mitigation 3: Reduction of Dust Related Impacts Mitigation 5: Reduction of Noise Related Impacts Mitigation 7: Vegetation Clearance	None	To be confirmed on completion of surveys
Small Mammals excl. bats (Irish Hare, Hedgehog, Wood	Local Importance	Construction Phase: Habitat loss.	Negative	Local	Permanent	Moderate (neutral or slight)	Mitigation 3: Reduction of dust related impacts	Enhancement 4: Hibernacula	Negative, Local, Permanent, Neutral or Slight

Key Ecological	Level of	Impact without mitigation Level of Potential		n	Proposed mitigation /	ion / Proposed					
Resources	Significance	Impact	Quality	Magnitude /Extent	Duration	Significance	mitigation / mitigation factors	enhancements (if any)	Residual impact		
Mouse, Pygmy Shrew)				Risk of injury or death during vegetation clearance and / or entrapment	Negative	Local	Short-term	Moderate (neutral or slight)	Mitigation 5: Reduction of noise related impacts Mitigation 7:		
		in construction-related rubbish and excavations. Disturbance from noise, dust and/or lighting.	Negative	Local	Short-term	Moderate (neutral or slight)	Vegetation Clearance Mitigation 8: Waste Management Mitigation 9: Avoidance of accidental trapping of fauna.				
	Operational Phase: Disturbance due to human activity.	Phase: Disturbance due to human	Negative	Local	Permanent	Moderate (neutral or slight)	Mitigation 9: Avoidance of Accidental Trapping of Mammals				
Common Lizard	Local Importance	Construction Phase: Loss of habitat	Negative	Local	Permanent	Moderate (neutral or slight)	Mitigation 7: Vegetation Clearance	Enhancement 4: Hibernacula	Negative, Local. Permanent, Not Significant		

Key Ecological Level of		Level of Potential		Impact with	out mitigation	n	Proposed mitigation /	Proposed	
Resources	Significance		Quality	Magnitude /Extent	Duration	Significance	mitigation factors	enhancements (if any)	Residual impact
		Risk of injury or death during vegetation clearance and / or entrapment in construction- related rubbish	Negative	Local	Short-term	Moderate (neutral or slight)	Mitigation 8: Waste		
		Operational Phase: No potential impacts identified	Positive	Local	Permanen	Negligible (neutral or slight)	Management		

6.7 Monitoring

The monitoring measures that are required and/or proposed are the same for both Plot 1 (Luttrellstown Gate Phase 2) and Plot 2 (St. Mochta's LRD) Sites of the Proposed Development. Therefore, this section outlines monitoring measures for both plots of the Site.

Table 6.31 below provides a summary of the required monitoring and pre-works inspections during the Construction Phase, as well as any surveys that should be completed during the Operational Phase. The monitoring, inspections and surveys will ensure that the identified mitigation measures are implemented and maintained efficiently and have the desired effect of protecting the local ecology from adverse impacts.

Table 6.31: Monitoring and pre-works inspection for the identified mitigation measures during the Construction Phase of the Proposed Development to be carried out by a suitably qualifies ecologist or ecological clerk of works (highlighted in green) or by development contractor (no highlight)

Measure	Plot	Monitoring
	Construction Phase	
Mitigation 1: Tree Protection	Plot 1	To be monitored by contractor or
Willigation 1. Tree Protection	Plot 2	arborist.
Mitigation 2: Standard Surface	Plot 1	To be seen thought to continue to a
Water and Ground Water Protection Measures	Plot 2	To be monitored by contractor.
Mitigation 3: Reduction of Dust	Plot 1	To be associated and business associated
Related Impacts	Plot 2	To be monitored by contractor.
Mitigation 4: Invasive Species Removal	Plot 2	To be monitored by contractor.
Mitigation 5: Reduction of Noise	Plot 1	To be manitored by contractor
Related Impacts	Plot 2	To be monitored by contractor.
Mitigation 6: Construction Phase	Plot 1	To be monitored by contractor.
Lighting	Plot 2	To be monitored by contractor.
Mitigation 7. Vagatation Classans	Plot 1	Any Site vegetation clearance is
Mitigation 7: Vegetation Clearance	Plot 2	subject to supervision by an Ecologist and a phased approach.
Mitigation 8: Waste Management	Plot 1	To be monitored by contractor.
ivinigation 6. waste ividinagement	Plot 2	To be monitored by contractor.
Mitigation 9: Avoidance of	Plot 1	To be monitored by contractor.
Accidental Trapping of Fauna	Plot 2	To be monitored by contractor.
	Dist 4	The placement and construction of these structures should be carried
Enhancement 1: Hedgehog Highways	Plot 1	out under the supervision of an
	Plot 2	Ecologist to ensure they are fit for purpose.
Enhancement 2: Pollinator Habitat	Plot 1	The placement and construction of these structures should be carried out under the supervision of an

STEPHEN LITTLE & ASSOCIATES MAY 2025

	Plot 2	Ecologist to ensure they are fit for purpose.
Enhancement 3: Bat Boxes	Plot 1 Plot 2	The placement and construction of these structures should be carried out under the supervision of an Ecologist to ensure they are fit for purpose.
Enhancement 4: Hibernacula	Plot 1 Plot 2	The placement and construction of these structures should be carried out under the supervision of an Ecologist to ensure they are fit for purpose. Should any damage occur, the Ecologist will be contacted, and appropriate repairs or replacements will be made.
	Operational Phase	
Mitigation 10: Invasive Species management	Plot 1 Plot 2	An Invasive Species Survey will be carried out by a qualified Ecologist during the next botanical season after soft landscaping has been completed.
Mitigation 11: Bats	Plot 1 Plot 2	To be monitored by contractor and/or suitably qualified ecologist.
Enhancement 6: Long term Management of Hedgerows	Plot 1 Plot 2	To be monitored by contractor, qualified arborist and/or suitably qualified ecologist.

6.8 Interactions

There are interactions between this biodiversity chapter and the hydrology, and hydrogeology chapters due to the assessment impacts to designated sites and aquatic environments via hydrological and hydrogeological pathways. The groundwater and surface water impacts discussed in these chapters are considered applicable to this chapter with regard to S-P-R pathways. Any mitigation or considerations of the ground and surface water impacts contained within those chapters are relevant to the biodiversity assessment with regard to the aquatic environment.

6.9 Difficulties Encountered

Every effort has been made to provide a comprehensive description of both Sites of the Proposed Development. However, the following specific limitations apply to this assessment:

- An extensive search of available datasets for records of rare and protected species within proximity of the Proposed Development has been undertaken as part of this assessment. However, the records from these datasets do not constitute a complete species list. The absence of species from these datasets does not necessarily confirm an absence of species in the area.
- Any limitations encountered during the upcoming surveys will be included in this section once the full suite of surveys is completed.